



POWER AMPLIFIER SERVICE MANUAL

MACRO-TECH[®]-2400

©1996 by CROWN INTERNATIONAL, INC.

Mailing Address:
P.O. Box 1000
Elkhart, IN U.S.A. 46515-1000

Shipping Address:
57620 C.R. 105
Elkhart, IN U.S.A. 46517

Macro-Tech[®], ODEP[®] and Crown[®] are registered trademarks of Crown International, Inc.

The information furnished in this manual does not include all of the details of design, production, or variations of the equipment. Nor does it cover every possible situation which may arise during installation, operation or maintenance. If you need special assistance beyond the scope of this manual, please contact the Crown Technical Support Group.

Mail: P.O. Box 1000 Elkhart IN 46515-1000

Shipping: 57620 C.R. 105 Elkhart IN 46517

Phone: (800) 342-6939/(219) 294-8200

FAX: (219) 294-8301

CAUTION

TO PREVENT ELECTRIC SHOCK DO NOT REMOVE TOP OR BOTTOM COVERS. NO USER SERVICEABLE PARTS INSIDE. REFER SERVICING TO QUALIFIED SERVICE PERSONNEL. DISCONNECT POWER CORD BEFORE REMOVING REAR INPUT MODULE TO ACCESS GAIN SWITCH.

AVIS

À PRÉVENIR LE CHOC ÉLECTRIQUE N'ENLEVEZ PAS LES COUVERTURES. RIEN DES PARTIES UTILES À L'INTÉRIEUR. DÉBRANCHER LA BORNE AVANT D'OUVRIRE LA MODULE EN ARRIÈRE.

WARNING

TO REDUCE THE RISK OF ELECTRIC SHOCK, DO NOT EXPOSE THIS EQUIPMENT TO RAIN OR MOISTURE!

Table of Contents

Introduction	4
Parts Information	5
Specifications	6
Voltage Conversion	7
Circuit Theory	8
Electrical Checkout Procedures	13
Parts List (Non-Module)	17
Module and Schematic Information	20
Fuse Module Parts List	21
Q42742-9 Display Module Parts List	22
Q42875-7 Display Module Parts List	23
Q43442-5 Display Module Parts List	24
Q42670-2 Output Module Parts List	25
Q42887-2 Output Module Parts List	26
Q42985-4 Output Module Parts List	27
Q43194-2 Output Module Parts List	28
Q43358-3 Output Module Parts List	29
Q42667-8 Main Module Parts List	30
Q42737-9 Main Module Parts List	33
Q42753-6 Main Module Parts List	36
Q42777-5 Main Module Parts List	39
Q42982-1 Main Module Parts List	42
Q43037-3 Main Module Parts List	45
Q43132-2 Main Module Parts List	48
Q43272-6 Main Module Parts List	51
Q43257-7 Main Module Parts List	54

Introduction

This manual contains service information on Crown power amplifiers. It is designed to be used in conjunction with the applicable Owner's Manual. However, some important information is duplicated in this Service Manual in case the Owner's Manual is not readily available.

NOTE: THE INFORMATION IN THIS MANUAL IS INTENDED FOR USE BY AN EXPERIENCED TECHNICIAN ONLY!

Scope

This Service Manual is intended to apply to all versions of the MA-2400 amplifier including the Amcron MA-2401. The Parts Listings include parts specific for the US version and the European version (MA-2400E13). For parts specific only to other versions contact the Crown Technical Support Group for help in finding part numbers.

This Service Manual includes several sections. These sections include Parts Information, Specifications, Voltage Conversion, Circuit Theory, Electrical Test Procedures, Non-Module Parts Lists, and Module Parts Lists. Schematics are attached. Note that component parts with circuit board comprise a complete module. Module part numbers are always associated with a specific circuit board, although an unpopulated

circuit board may be built up with different parts to create different modules. Note that Crown does not sell blank (unpopulated) circuit boards.

Each of the compact audio power amplifiers are designed for professional or commercial use. Providing high power amplification from 20Hz to 20KHz with minimum distortion, they feature balanced inputs with bridged and parallel monophonic capability. Specific features vary depending on model family.

Warranty

Each Owner's Manual contains basic policies as related to the customer. In addition it should be stated that this service documentation is meant to be used only by properly trained service personnel. Because most Crown products carry a 3 Year Full Warranty (including round trip shipping within the United States), all warranty service should be referred to the Crown Factory or Authorized Warranty Service Center. See the applicable Owner's Manual for warranty details. To find the location of the nearest Authorized Service Center or obtain instructions for receiving Crown Factory Service please contact the Crown Technical Support Group (within North America) or your Crown/Amcron Importer (outside North America).

**Crown
Technical Support Group
Factory Service
Parts Department**

Mailing Address:
PO Box 1000
Elkhart, IN USA 46515-1000

Shipping Address:
57620 C.R. 105
Elkhart, IN USA 46517

Phone: (219) 294-8200
Toll Free: (800) 342-6939
FAX: (219) 294-8301

Parts Information

General Information

Later sections include both mechanical and electrical parts lists for this product. The parts listed are current as of the date printed. Crown reserves the right to modify and improve its products for the benefit of its customers.

Part Numbering Systems

As of the printing of this manual, Crown is using two numbering systems. The elder system always uses eight characters. The first character is a letter. Common letters used are C, D, H, M, P, and Q. The second through sixth characters are numbers. The numbers build sequentially (for each prefix letter) as new parts are added to our parts inventory system. (In some cases there will be a space then a four character number after the prefix letter; the space is considered a character.) The seventh character is usually a hyphen, though it may be a letter to indicate a revision or special note. The last character is called a check-digit, and is useful to Crown for internal tracking.

Crown is in the process of converting to a new part number system. Length may vary from eight to twelve characters. There is still a letter prefix, then five numbers. These five numbers identify a type of part. The seventh character is a hyphen. Remaining characters identify the details of the type of part identified by the first part of the number.

Standard and Special Parts

Many smaller electrical and electronic parts used by Crown are stocked by and available from electronic supply houses. However, some electronic parts that appear to be standard are actually special. A part ordered from Crown will assure an acceptable replacement. Structural items such as modules and panels are available from Crown only.

Ordering Parts

When ordering parts, be sure to give the product model, and include a description and part number (CPN/DPN) from the parts listing. Price quotes are available on request.

Shipment

Shipment will be normally made by UPS or best other method unless you specify otherwise. Shipments are made to and from Elkhart, Indiana USA, only. Established accounts with Crown will receive shipment freight prepaid and will be billed. All others will receive

shipment on a C.O.D. or pre-payment (check or credit card) basis.

Terms

Normal terms are pre-paid. Net-30 Days applies to only those firms having pre-established accounts with Crown. If pre-paying, the order must be packed and weighed before a total bill can be established, after which an amount due will be issued and shipment made upon receipt of pre-payment. New parts returned for credit are subject to a 10% re-stocking fee, and authorization from the Crown Parts Department must be obtained before returning parts for credit.

Crown is not a general parts warehouse. Parts sold by the Crown Parts Department are solely for servicing Crown/Amcron products. **Part prices and availability are subject to change without notice.**

Crown Parts Department

Mailing Address:
PO Box 1000
Elkhart, IN USA 46515-1000

Shipping Address:
57620 C.R. 105
Elkhart, IN USA 46517

Phone: (219) 294-8210
or: (219) 294-8211
Toll Free: (800) 342-6939
FAX: (219) 294-8301

Specifications

Unless noted otherwise, all specifications are based on driving an 8 ohm load per channel, both channels driven, the sensitivity switch in the 26dB position, the AC supply is 120VAC at 60Hz. Crown specifications are guaranteed through the warranty period (normally 3 years). Because our testing methods are more stringent than our published specifications, every Crown amplifier will exceed its published specifications.

POWER

Power

8 Ohm Stereo—520W/Ch
4 Ohm Stereo—800W/Ch
2 Ohm Stereo—1050W/Ch
8 Ohm Bridge Mono—1585W
4 Ohm Bridge Mono—2070W
2 Ohm Parallel Mono—1605W
1 Ohm Parallel Mono—2080W

Load Impedances: Rated for 16, 8, 4, 2, and 1 (parallel mono only) Ohm operation; safe with all types of loads, even totally reactive loads.

AC Mains: 120VAC at 60 Hz with Nema standard 5-20P 20 Amp grounded connector for North American units; 100VAC, 120VAC, 220VAC, and 240VAC at 50 or 60 Hz when equipped with universal transformers, applicable fan assembly, and other applicable hardware with country specific power cord.

PERFORMANCE

Frequency Response: ± 0.1 dB from 20 Hz to 20 kHz at 1 Watt.

Phase Response: $\pm 10^\circ$ from 10 Hz to 20 kHz at 1 Watt.

Signal to Noise Ratio: A-weighted, better than 105 dB below full rated output. Better than 100 dB below full rated output from 20 Hz to 20 kHz.

Total Harmonic Distortion (THD): $< 0.05\%$ from 20 Hz to 1 kHz, increasing linearly to 0.1% at 20 kHz at 500W.

I.M. Distortion: $< 0.05\%$ from less than 164 milliwatts to 520 W at 26 dB gain.

Slew Rate: > 13 V per microsecond. (Slew rates are limited to useful levels for ultrasonic/RF protection.)

Damping Factor: > 1000 from 10 Hz to 400 Hz.

DC Offset: < 10 millivolts.

Input Impedance: Nominally 20K ohms balanced; 10K ohms unbalanced.

Output Impedance: < 10 milliohms in series with < 2 microhenries.

Protection Systems: Output Device Emulation Protection (ODEP) limits drive in the event of dangerous dynamic thermal conditions without interrupting power. Current limiting for shorted load protection. DC/LF and common mode output current Fault circuitry to mute audio. Delay of 4 seconds from turn on mutes amplifier to prevent dangerous turn-on transients. A high voltage fuse in each main transformer primary and a low voltage power supply fuse in fan primary. Slew rate limiting to prevent RF burn out.

MECHANICAL

Input Connectors: Balanced 1/4 inch phone jacks. Balanced female XLR connector for each channel on the standard P.I.P.-FX module.

Output Connectors: Color-coded 5-way binding posts on 3/4 inch centers; spaced 3/4 inch apart.

Front Panel Controls: A front panel push button switch used to power the amplifier on and off. A detented front panel rotary potentiometer for each channel used to control the output level.

Back Panel Controls: A three-position switch which selects Stereo, Bridge-Mono, or Parallel-Mono mode. A ground lift switch used to isolate the phone jack input grounds from the chassis (AC) ground.

Internal Controls: A three-position switch located inside the P.I.P compartment selects 0.775V, 1.4V, or 26 dB voltage gain input sensitivity.

Indicators: Amber Enable indicator shows on/off status of low-voltage power supply. An Amber ODEP indicator for each channel shows the reserve energy status. If no reserve energy is available the indicator will dim in proportion to ODEP limiting. A green SIGNAL/IOC two function indicator for each channel flashes to show that there is amplifier output. The indicator flashes with brighter intensity if the amplifier causes any distortion of 0.05% or more.

Construction: Black splatter-coat steel chassis with specially designed flow-through ventilation system.

Mounting: Standard EIA 310 front-panel rack mount with supports for supplemental rear corner mounting.

Dimensions: 19 inches wide, 3.5 inches high, 16 inches deep behind front mounting surface.

Weight: 51 lbs, 12 oz (23.5 kg). Shipping; 65 lbs (29.5 kg).

Voltage Conversion

The 120 Volt 60 Hz version, sold in the United States, is not voltage selectable. It does not have voltage selection boards. This version is to be used only with 120 Volts, 60Hz.

All other versions of the Macro Tech 2400 use voltage selection boards. The following chart indicates which jumpers are used for different voltages. Note that the fuses and transmotor may need to be changed to accommodate different voltages. Versions with the voltage selection boards may be used at 50 or 60 Hz.

VOLTAGE SELECTION BOARD

	100V	120V	200V	220V/230V	240V
Jumpers	ORG—B B—E BLU—F C—F	ORG—A A—D BLU—F C—F	ORG—B C—E BLU—F	ORG—B C—D BLU—F	ORG—A C—D BLU—F
Circuit Breakers CB100/CB200	C10169-8 15 Amp		C10171-4 8 Amp		
Fuse F1	A10285-10 1 Amp		A10285-7 .5 Amp		
Transmotor TF1	H42999-5	H42929-2	H42928-4		

Theory

Overview

It should be noted that over time Crown makes improvements and changes to their products for various reasons. This manual is up to date as of the time of writing. For additional information regarding these amplifiers, refer to the applicable Technical Notes provided by Crown for this product.

This section of the manual explains the general operation of a typical Crown power amplifier. Topics covered include Front End, Grounded Bridge, and ODEP. Due to variations in design from vintage to vintage (and similarities with other Crown products) the theory of operation remains simplified.

Features

Macro Tech amplifiers utilize numerous Crown innovations including grounded bridge and ODEP technologies. Cooling techniques make use of the what is essentially air conditioner technology. Air flows bottom to top, and front to side. Air flows a short distance across a wide heatsink. This type of air flow provides significantly better cooling than the "wind tunnel" technology used by many other manufacturers. Output transistors are of the metal can type rather than plastic case. This allows for a significantly higher thermal margin for the given voltage and current ratings. All devices used are tested and graded to ensure maximum reliability. Another electronic technique used is negative feedback. Almost all power amplifiers utilize negative feedback to control gain and provide stability, but Crown uses multiple nested feedback loops for maximum stability and greatly improved damping. Most Crown amplifiers have damping in excess of 1000 in the bass frequency range. This feedback, along with our compensation and ultra-low distortion output topology, make Crown amplifiers superior.

Features specific to the Macro Tech Series' include two separate power transformers (one for each channel), a full time full speed fan which also serves as the low voltage transformer, slew rate limiting, and audio muting for delay or protective action. This amplifier can operate in either a Bridged or Parallel Mono mode as well as dual (stereo). A sensitivity switch allows selection of input voltage required for rated output. Level controls are mounted on the front panel and are of the rotary type. Front panel indicators let the user know the status of the low voltage power supply (enable), an ODEP indicator for each channel which shows the reserve energy status, and a SPI/IOC

indicator for each channel which indicates signal output and distortion. In general, the packaging of this model is designed for maximum watt/price/weight/size value with user friendly features.

For additional details refer to the specification section, or to the applicable Owner's Manual.

Front End Operation

The front end is comprised of three stages: Balanced Gain Stage (BGS), Variable Gain Stage (VGS), and the Error Amp. Figure 1 shows a simplified diagram of a typical front end with voltage amplification stages.

Balanced Gain Stage (BGS)

Input to the amplifier is balanced. The shield may be isolated from chassis ground by an RC network to interrupt ground loops via the Ground Lift Switch. The non-inverting (hot) side of the balanced input is fed to the non-inverting input of the first op-amp stage. The inverting (negative) side of the balanced input is fed to the inverting input of the first op-amp stage. A potentiometer is provided for common mode rejection adjustment. Electrically, the BGS is at unity gain. (From an audio perspective, however, this stage actually provides +6dB gain if a fully balanced signal is placed on its input.) The BGS is a non-inverting stage. Its output is delivered to the Variable Gain Stage.

Variable Gain Stage (VGS)

From the output of the BGS, the signal goes to the VGS where gain is determined by the position of the Sensitivity Switch, and level is determined by the level control. VGS is an inverting stage with the input being fed to its op-amp stage. Because gain after this stage is fixed at 26dB (factor of 20), greater amplifier sensitivity is achieved by controlling the ratio of feedback to input resistance. The Sensitivity Switch sets the input impedance to this stage and varies the gain such that the overall amplifier gain is 26 dB, or is adjusted appropriately for 0.775V or 1.4V input to attain rated output.

Error Amp

The inverted output from the VGS is fed to the non-inverting input of the Error Amp op-amp stage through an AC coupling capacitor and input resistor. Amplifier output is fed back via the negative feedback (NFB) loop resistor. The ratio of feedback resistor to input resistor fixes gain from the Error Amp input to the output of the amplifier at 26 dB. Diodes prevent

Theory

overdriving the Error Amp. Because the Error Amp amplifies the difference between input and output signals, any difference in the two waveforms will produce a near open loop gain condition which in turn results in high peak output voltage. The output of the Error Amp, called the Error Signal (ES) drives the Voltage Translators.

Voltage Amplification

The Voltage Translator stage separates the output of the Error Amp into balanced positive and negative drive voltages for the Last Voltage Amplifiers (LVAs), translating the signal from ground referenced $\pm 15V$ to $\pm V_{CC}$ reference. LVAs provide the main voltage amplification and drive the High Side output stages. Gain from Voltage Translator input to amplifier output is a factor of 25.2.

Voltage Translators

A voltage divider network splits the Error Signal (ES) into positive and negative drive signals for the balanced voltage translator stage. These offset reference voltages drive the input to the Voltage Translator transistors. A nested NFb loop from the output of the amplifier mixes with the inverted signal riding on the offset references. This negative feedback fixes gain at the offset reference points (and the output of the Error Amp) at a factor of -25.2 with respect to the amplifier output. The Voltage Translators are arranged in a common base configuration for non-inverting voltage gain with equal gain. They shift the audio from the $\pm 15V$ reference to VCC reference. Their outputs drive their respective LVA.

Also tied into the Voltage Translator inputs are ODEP

limiting transistors and control/protection transistors. The ODEP transistors steal drive as dictated by the ODEP circuitry (discussed later). The control/protection transistors act as switches to totally shunt audio to ground during the turn-on delay, or during a DC/LF or Fault protective action.

Last Voltage Amplifiers (LVAs)

The Voltage Translator stage channels the signal to the Last Voltage Amplifiers (LVA's) in a balanced configuration. The +LVA and -LVA, with their push-pull effect through the Bias Servo, drive the fully complementary output stage. The LVAs are configured as common emitter amplifiers. This configuration provides sufficient voltage gain and inverts the audio. The polarity inversion is necessary to avoid an overall polarity inversion from input jack to output jack, and it allows the NFb loop to control Error Amp gain by feeding back to its non-inverting input (with its polarity opposite to the output of the VGS). With the added voltage swing provided by the LVAs, the signal then gains current amplification through the Darlington emitter-follower output stage.

Grounded Bridge Topology

Figure 2 is a simplified example of the grounded bridge output topology. It consists of four quadrants of three deep Darlington (composite) emitter-follower stages per channel: one NPN and one PNP on the High Side of the bridge (driving the load), and one NPN and one PNP on the Low Side of the bridge (controlling the ground reference for the rails). The output stages are biased to operate class AB+B for ultra low distortion in the signal zero-crossing region and high efficiency.




Figure 1. Typical Amplifier Front End and Voltage Amplification Stages.

Theory

High Side (HS)

The High Side (HS) of the bridge operates much like a conventional bipolar push-pull output configuration. As the input drive voltage becomes more positive, the HS NPN conducts and delivers positive voltage to the load. Eventually the NPN devices reach full conduction and $+V_{cc}$ is across the load. At this time the HS PNP is biased off. When the drive signal is negative going, the HS PNP conducts to deliver $-V_{cc}$ to the load and the HS NPN stage is off.

The output of the +LVA drives the base of predriver device. Together, the predriver and driver form the first two parts of the three-deep Darlington and are biased class AB. They provide output drive through the bias resistor, bypassing the output devices, at levels below about 100mW. An RLC network between the predriver and driver provide phase shift compensation and limit driver base current to safe levels. Output devices are biased class B, just below cutoff. At about 100mW output they switch on to conduct high current to the load. Together with predriver and driver, the output device provide an overall class AB+B output.

The negative half of the HS is almost identical to the positive half, except that the devices are PNP. One difference is that the PNP bias resistor is slightly greater in value so that PNP output devices run closer to the cutoff level under static (no signal) conditions.

This is because PNP devices require greater drive current.

HS bias is regulated by Q18, the Bias Servo. Q18 is a V_{be} multiplier which maintains approximately 3.3V V_{ce} under static conditions. The positive and negative halves of the HS output are in parallel with this 3.3V. With a full base-emitter on voltage drop across predrivers and drivers, the balance of voltage results in approximately .35V drop across the bias resistors in the positive half, and about .5V across the bias resistor in the negative half. Q18 conduction (and thus bias) is adjustable.

A diode string prevents excessive charge build up within the high conduction output devices when off. Flyback diodes shunt back-EMF pulses from reactive loads to the power supply to protect output devices from dangerous reverse voltage levels. An output terminating circuit blocks RF on output lines from entering the amplifier through its output connectors.

Low Side (LS)

The Low Side (LS) operates quite differently. The power supply bridge rectifier is not ground referenced, nor is the secondary of the main transformer. In other words, the high voltage power supply floats with respect to ground, but $\pm V_{cc}$ remain constant with respect to each other. This allows the power supply to




Figure 2. Crown Patented Grounded Bridge Topology

Theory

deliver +Vcc and -Vcc from the same bridge rectifier and filter as a total difference in potential, regardless of their voltages with respect to ground. The LS uses inverted feedback from the HS output to control the ground reference for the rails ($\pm V_{cc}$). Both LS quadrants are arranged in a three-deep Darlington and are biased AB+B in the same manner as the HS.

When the amplifier output swings positive, the audio is fed to an op-amp stage where it is inverted. This inverted signal is delivered directly to the bases of the positive (NPN) and negative (PNP) LS predrivers. The negative drive forces the LS PNP devices on (NPN off). As the PNP devices conduct, Vce of the PNP Darlington drops. With LS device emitters tied to ground, -Vcc is pulled toward ground reference. Since the power supply is not ground referenced (and the total voltage from +Vcc to -Vcc is constant) +Vcc is forced higher above ground potential. This continues until, at the positive amplifier output peak, -Vcc = 0V and +Vcc equals the total power supply potential with a positive polarity. If, for example, the power supply produced a total of 70V from rail to rail ($\pm 35V_{DC}$ measured from ground with no signal), the amplifier output would reach a positive peak of +70V.

Conversely, during a negative swing of the HS output where HS PNP devices conduct, the op-amp would output a positive voltage forcing LS NPN devices to conduct. This would result in +Vcc swinging toward ground potential and -Vcc further from ground potential. At the negative amplifier output peak, +Vcc = 0V and -Vcc equals the total power supply potential with a negative polarity. Using the same example as above, a 70V supply would allow a negative output peak of -70V. In summary, a power supply which produces a total of 70VDC rail to rail (or $\pm 35V_{DC}$ statically) is capable of producing 140V peak-to-peak at the amplifier output when the grounded bridge topology is used. The voltage used in this example are relatively close to the voltages of the PB-1/460CSL.

The total effect is to deliver a peak to peak voltage to the speaker load which is twice the voltage produced by the power supply. Benefits include full utilization of the power supply (it conducts current during both halves of the output signal; conventional designs require two power supplies per channel, one positive and one negative), and never exposing any output device to more than half of the peak to peak output voltage (which does occur in conventional designs).

Low side bias is established by a diode string which also shunts built up charges on the output devices. Bias is adjustable via potentiometer. Flyback diodes perform the same function as the HS flybacks. The output of the LS is tied directly to chassis ground via ground strap.

Output Device Emulation Protection (ODEP)

To further protect the output stages, a specially developed ODEP circuit is used. It produces a complex analog output signal. This signal is proportional to the always changing safe-operating-area margin of the output transistors. The ODEP signal controls the Voltage Translator stage by removing drive that may exceed the safe-operating-area of the output stage.

ODEP senses output current by measuring the voltage dropped across LS emitter resistors. LS NPN current (negative amplifier output) and +Vcc are sensed, then multiplied to obtain a signal proportional to output power. Positive and negative ODEP voltages are adjustable via two potentiometers. Across $\pm ODEP$ are a PTC and a thermal sense (current source). The PTC is essentially a cutoff switch that causes hard ODEP limiting if heatsink temperature exceeds a safe maximum, regardless of signal level. The thermal sense causes the differential between +ODEP and -ODEP to decrease as heatsink temperature increases. An increase in positive output signal output into a load will result in -ODEP voltage dropping; an increase in negative output voltage and current will cause +ODEP voltage to drop. A complex RC network between the $\pm ODEP$ circuitry is used to simulate the thermal barriers between the interior of the output device die (immeasurable by normal means) and the time delay from heat generation at the die until heat dissipates to the thermal sensor. The combined effects of thermal history and instantaneous dynamic power level result in an accurate simulation of the actual thermal condition of the output transistors.

Theory




Figure 3. Typical Crown Amplifier Basic Block Diagram (One Channel Shown)

Electrical Checkout Procedures

General Information

The following test procedures are to be used to verify operation of this amplifier. DO NOT connect a load or inject a signal unless directed to do so by the procedure. These tests, though meant for verification and alignment of the amplifier, may also be very helpful in troubleshooting. For best results, tests should be performed in order.

All tests assume that AC power is from a regulated 120 VAC source. Test equipment includes an oscilloscope, a DMM, a signal generator, loads, and I.M.D. and T.H.D. noise test equipment.

Standard Initial Conditions

Level controls fully clockwise.

Stereo/Mono switch in Stereo.

Sensitivity switch in 26 dB fixed gain position.

It is assumed, in each step, that conditions of the amplifier are per these initial conditions unless otherwise specified.

Test 1: DC Offset

Spec: 0 VDC, ± 10 mV.

Initial Conditions: Controls per standard, inputs shorted.

Procedure: Measure DC voltage at the output connectors (rear panel). There is no adjustment for output offset. If spec is not met, there is an electrical malfunction. Slightly out of spec measurement is usually due to U104/U204 out of tolerance.

Test 2: Output Bias Adjustment

Spec: 300 to 320 mVDC.

Initial Conditions: Controls per standard, heatsink temperature less than 40°C.

Procedure: Measure DC voltages on the output module across R02, adjust R26 if necessary. Measure DC voltages on the output module across R21, adjust R23 if necessary. Repeat for second channel.

Test 3: ODEP Voltage Adjustment

Spec: Bias Per Chart, ± 0.1 V DC.

Initial Conditions: Controls per standard, heatsink at room temperature 20 to 30°C (68 to 86°F). Note: This adjustment should normally be performed within 2 minutes of turn on from ambient (cold) conditions. If possible measure heatsink temperature, if not measure ambient room temperature. Use this information when referencing the following charts.

The following list of ODEP bias voltages VS. temperature is based on the use of Main Modules built on any circuit board up to and including the D 7993-5 board.

°F	°C	V _{-ODEP}	V _{+ODEP}
66	18.9	-10.31	11.41
68	20.0	-10.26	11.36
70	21.1	-10.20	11.30
72	22.2	-10.14	11.24
74	23.3	-10.09	11.19
76	24.4	-10.03	11.13
77	25.0	-10.00	11.10
78	25.6	-9.97	11.07
80	26.7	-9.91	11.01
82	27.8	-9.86	10.96
84	28.9	-9.80	10.90
86	30.0	-9.74	10.84
88	31.1	-9.69	10.79
90	32.2	-9.63	10.73
92	33.3	-9.57	10.67
94	34.4	-9.51	10.61

The following list of ODEP bias voltages VS. temperature is based on the use of Main Modules built on any circuit board after the D 7993-5 board.

°F	°C	V _{-ODEP}	V _{+ODEP}
66	18.9	-10.31	10.31
68	20.0	-10.26	10.26
70	21.1	-10.20	10.20
72	22.2	-10.14	10.14
74	23.3	-10.09	10.09
76	24.4	-10.03	10.03
77	25.0	-10.00	10.00
78	25.6	-9.97	9.97
80	26.7	-9.91	9.91
82	27.8	-9.86	9.86
84	28.9	-9.80	9.80
86	30.0	-9.74	9.74
88	31.1	-9.69	9.69
90	32.2	-9.63	9.63
92	33.3	-9.57	9.57
94	34.4	-9.51	9.51

-ODEP Procedure: Measure pin 6 of U100 and, if necessary, adjust R121 to obtain V_{-ODEP} as specified above. Measure pin 6 of U200 and, if necessary, adjust R221 to obtain V_{-ODEP} as specified above.

+ODEP Procedure: Measure pin 6 of U103 and, if necessary, adjust R132 to obtain V_{+ODEP} as specified above. Measure pin 6 of U203 and, if necessary, adjust R232 to obtain V_{+ODEP} as specified above.

Electrical Checkout Procedures

Test 4: AC Power Draw

Spec: 100 Watts maximum quiescent.

Initial Conditions: Controls per standard.

Procedure: With no input signal and no load, measure AC line wattage draw. If current draw is excessive, check for high AC line voltage or high bias voltage.

Test 5: Common Mode Rejection

Spec at 100 Hz: -70 dB.

Spec at 20 kHz: -50 dB.

Initial Conditions: Controls per standard.

Procedure: No load. Inject a 0 dBu (.775VRMS) 100 Hz sine wave into each channel, one channel at a time, with inverting and non-inverting inputs shorted together. At the output measure less than -44 dBu (4.9mVRMS). Inject a 0 dBu 20 kHz sine wave into each channel, one channel at a time, with inverting and non-inverting inputs shorted together. At the output measure less than -24 dBu (49mVRMS). For Main Modules with board numbers lower than D 7993-5 adjust N100 and N200 to calibrate CMR. For Main Modules with board number D 7993-5 or greater adjust R921 and R1021.

Test 6: Voltage Gain

Spec 26dB Gain: Gain of 20.0 \pm 3%.

Spec 0.775V Sensitivity: \pm 10%.

Spec 1.4V Sensitivity: \pm 10%.

Initial Conditions: Controls per standard.

Procedure: No load connected. Inject a 0.775 VAC 1 kHz sine wave with the Sensitivity Switch in the 26 dB position. Measure 15.5 VAC \pm 0.5 VAC at the amplifier output. Inject a 0.775 VAC 1 kHz sine wave with the Sensitivity Switch in the 0.775V position. Measure 64 VAC \pm 6 VAC at the amplifier output. Inject a 1.4 VAC 1 kHz sine wave with the Sensitivity Switch in the 1.4V position. Measure 64 VAC \pm 6 VAC at the amplifier output. Return the Sensitivity Switch to the 26 dB position.

Test 7: Phase Response

Spec: \pm 10° from 10 Hz to 20 kHz at 1 Watt.

Initial Conditions: Controls per standard, 8 ohm load on each channel.

Procedure: Inject a 1 kHz sine wave and adjust for 1 Watt output (2.8 VAC). Check input and output signals against each other, input and output signals must be within 10° of each other.

Test 8: Level Controls

Spec: Level controlled by level controls.

Initial Conditions: Controls per standard.

Procedure: No Load. Inject a 1 kHz sine wave. With level controls fully clockwise you should see full gain. As controls are rotated counterclockwise, observe similar gain reduction in each channel. When complete, return level controls to fully clockwise position.

Test 9: Current Limit

Spec: Current Limit at 36 Amps, \pm 5 Amps

Initial Conditions: Controls per standard.

Procedure: Load each channel to 1 Ohm. Inject a 1 kHz differentiated (or 10% duty cycle) square wave. See figure 4. Increase output level until current limit occurs. Current limit should occur at 36 \pm 5 Amps (36 Vpk). Observe clean (no oscillations) current clipping.




Figure 4. Differentiator Circuit

Test 10: Slew Rate & 10 kHz Square Wave

Spec: 17 - 25 V/ μ S.

Initial Conditions: Controls per standard.

Procedure: Load each channel to 8 ohms. Inject a 10 kHz square wave to obtain 65 volts zero-to-peak at each output. Observe the slope of the square wave. It should typically measure 13 to 15 V/ μ S. Also, the square wave must not include overshoot, ringing, or any type of oscillation.

Test 11: Crosstalk

Spec: -60dB at 20 kHz.

Initial Conditions: Controls per standard. Terminate input of channel not driven with 600 ohms.

Procedure: 8 ohm load on each channel. Inject a 20 kHz sine wave into the Channel 1 input and increase output level to 63 VAC. Measure less than 63 mVAC at the output of Channel 2. Inject a 20 kHz sine wave into the Channel 2 input and increase output level to 63 VAC. Measure less than 63 mVAC at the output of Channel 1.

Electrical Checkout Procedures

Test 12: Output Power

Spec at 8 Ohm Stereo: $\geq 520\text{W}$ at 0.1% THD.

Spec at 4 Ohm Stereo: $\geq 800\text{W}$ at 0.1% THD.

Spec at 2 Ohm Stereo: $\geq 1050\text{W}$ at 0.1% THD.

International 8 Ohm Stereo: $\geq 510\text{W}$ at 0.1% THD.

International 4 Ohm Stereo: $\geq 745\text{W}$ at 0.1% THD.

International 2 Ohm Stereo: $\geq 895\text{W}$ at 0.1% THD.

Initial Conditions: Controls per standard.

Procedure: Load each channel to 8 ohms. Inject a 1 kHz sine wave and measure at least 64.50 VAC at the output of each channel. Load each channel to 4 ohms. Inject a 1 kHz sine wave and measure at least 56.57 VAC. Load each channel to 2 ohms. Inject a 1 kHz sine wave and measure at least 45.82 VAC. All power measurements must be at less than 0.1% THD.

Test 13: Reactive Loads

Spec: No oscillations. Safe with all types of loads.

Initial Conditions: Controls per standard.

Procedure Capacitive: Load each channel to 8 ohms in parallel with 2 μF . Inject a 20 kHz sine wave with 55 VAC output for 10 seconds.

Procedure Inductive: Load each channel to 8 ohms in parallel with 159 μH enries. Inject a 1 kHz sine wave with 35.8 VAC output for 10 seconds.

Procedure Torture: Load each channel with the primary (red and black leads) of a DC-300A transformer (D 5781-6). Inject a 15 Hz sine wave at sufficient output level to cause 3 to 5 flyback pulses, for 10 seconds.

Procedure Short: Inject a 60 Hz sine wave with a minimum of 5 VAC at the amplifier output. After establishing signal, short the output for 10 seconds.

Test 14: ODEP Limiting

Spec: No oscillation on ODEP Limiting wave form; either channel controls limiting in Parallel Mono Mode.

Initial Conditions: Controls per standard; rag or other obstruction blocking fan so that it does not turn.

Procedure: Load the amplifier to 2 ohms on each channel. Inject a 60 Hz sine wave and adjust for 28 Vrms at the output. After a few minutes observe a wave form similar to Figure 5. Remove the input signal from both channels and allow the amplifier to cool for a few minutes. Switch the amplifier to Parallel Mono and remove the load from Channel 1. Inject the signal into Channel 1 and observe that ODEP limiting occurs at the output of both channels. Remove the load from Channel 2, and install the load on Channel 1. Again, observe that both channels limit. Return all amplifier controls to standard initial conditions. Remove the fan obstruction.




Figure 5. ODEP Limiting Wave Form

Test 15: LF Protection

Spec: Amplifier mutes for low frequency.

Initial Conditions: Controls per standard.

Procedure: No load. Inject a 0.5 Hz 6 volt peak-to-peak square wave, or a 2 Hz 6VAC sine wave into each channel and verify that each channel cycles into mute.

Test 16: Signal to Noise Ratio

Spec: 100 dB below rated 8 ohm power 20 Hz to 20 kHz. 105 dB A-Weighted.

Initial Conditions: Controls per standard. Short inputs.

Procedure: Load each channel to 8 ohms. Measure less than 645 μV at the output of each channel (20 Hz-20 kHz bandpass filter).

Test 17: Turn On Transients

Spec: No dangerous transients.

Initial Conditions: Controls per standard.

Procedure: From an off condition, turn on the amplifier and monitor the output noise at the time of turn on. Note: Turn on noise may increase significantly if the amplifier is cycled off and on.

Electrical Checkout Procedures

Test 18: Turn Off Transients

Spec: No dangerous transients.

Initial Conditions: Controls per standard.

Procedure: From an on condition, turn off the amplifier and monitor the output noise at the time of turn off.

Note: Turn off noise may increase significantly if the amplifier is cycled off and on.

Test 19: Intermodulation Distortion

Spec at 0 dB Output: 0.01%.

Spec at -35 dB Output: 0.05%.

Initial Conditions: Controls per standard.

Procedure: Load each channel to 8 ohms. Inject a SMPTE standard IM signal (60 Hz and 7 kHz sine wave mixed at 4:1 ratio). Set the 60 Hz portion of the sine wave to 50.8 Volt RMS. Set the 7 kHz portion to 25%. With an IM analyzer measure less than 0.01% IMD. Repeat test at -35 dB (reference 50.8 Volt RMS, 60 Hz portion) and measure less than 0.05% IMD.

Test 20: Clipping

Spec: No protective action during test.

Initial Conditions: Controls per standard.

Procedure: Load each channel to 8 ohms. Inject a 1 kHz sine wave at each input and drive output 6 dB into clip for 10 seconds. The amplifier should not activate any protective circuits (ODEP, Fault, or LF Protection).

Post Testing

After completion of testing, if all tests are satisfactory, the amplifier controls should be returned to the positions required by customer. If conditions are unknown or unspecified, factory settings are as follows:

Level Controls: 9 to 11 O'Clock.

Sensitivity Switch: 0.775V U.S., 1.4V International.

Stereo/Mono Switch: Stereo.

Ground Lift: Lift.

Power: Off.

Parts List (Non-Module)

Supplimental Items

CPN	ITEM	QTY
D 4137-2	Nylon Thumbscrew Washer	4
C 3342-0	Feet, Black Self-Stick	4
A10087-71012	10-32 .75 Machine (Rack Screw)	4
K80449D2	MA Series Owners Manual	1

Power Supply

CPN	ITEM	QTY
D 6974-6	Insulator, Fuse Board	1
A10089-11032	Screw, 10-32 x 2 (for transformers)	8
A10094-8	Washer, #10 Int Star, Zinc (transformers)	8
A10099-7	Shoulder Washer, #10 Nylon (transformers)	8
A10100-16	Washer, 7/16OD x .203ID (transformers)	8
A10102-8	Nut, 10-32 Hex Zinc (transformers)	8
A10094-8	Lockwasher, #10 Internal Tooth	4
A10098-5	Washer, 1/4" Belleville Spring	4
C 8752-5	35A 400V Bridge Rectifier	2
C 9870-4	Screw, 10-32 x .38	4
D 6764-1	Washer, Shoulder	4
D 8438-0	Bracket, Capacitor	2
D 8639-3	6300uF 150V Electrolytic Capacitor	2
A10285-10	Fuse, 1A (100V-120V)	1
A10285-7	Fuse, .5A (200V-240V)	1
C10169-8	Breaker, 15A (100V-120V)	2
C10171-4	Breaker, 8A (200V-240V)	2
D 8993-4	Transformer, Power (120V, 60Hz)	2
D 9017-1	Transformer, Power (Universal Volt)	2
H42875-7	Transmotor (120V 60Hz)	1
H42928-4	Transmotor (200V-240V)	1

Output Assembly (One Per Channel)

CPN	ITEM	QTY (PER CHANNEL)
A10315-1	Screw, 6-32 x .56 Hex Washer Head, Torx	12
C 8187-4	NPN Power Transistor	6
C 8188-2	PNP Power Transistor	6
C 9387-9	Plasti-Rivit, .156 2 Prong Black	2
C 9491-9	Screw, 6-32 x .312 Pan Head	27
D 7796-2	Sil Pad (between heatsink and chassis)	1
	-For units with P10315-3 output boards use D 6280-8	
	-For units with boards older than P10315-3 use D 6104-0	
D 7797-0	Pad (between module and chassis)	1
	-For units with P10315-3 output boards use C 7597-4	
	-For units with boards older than P10315-3 use D 7026-4	
D 8197-2	Paper Shroud, 1.75 x 14.45	1
D 8774-8	PTC, 95DegC Cast Alum	1
F12019-0	Heatsink Under Bias Diodes	1
B 5842-8	Tubing, #23 TFE (For Q18)	Order in Inches
C 8813-5	MPS8097/MPSA18 (Q18)	1
B 5464-1	Tubing, #24 Teflon, Thin Wall (For S100/S200)	Order in Inches
C 5826-0	LM234Z-6 Thermal Sense (S100/S200)	1

Parts List (Non-Module)

Output Assembly (cont.)

CPN	ITEM	QTY (ONE PER CHANNEL)
M21322J8	Heat Sink with Fins	2
C 8573-5	2SA1186 PNP Driver Transistor	2
C 8574-3	2SC2837 NPN Driver Transistor	2
D 7665-9	T03P Mounting Clip	2
D 7666-7	T03P Bracket	2

Back Panel Assembly

CPN	ITEM	QTY
D 7975-2	Power Cord, 12/3 SO/W-A 20A U.S. Models)	1
A10793-0503G	Power Cord (European Models)	1
M44018-6	PIP-FX	1
A10086-10410	Screw, 4-40 x .62	2
A10086-11008	Screw, 10-32 x .5	1
A10094-2	Lockwasher, #4 Internal Star	2
A10095-4	Lockwasher, #10 Internal Star	1
A10100-7	Aluminium Spacer, .250OD x .140ID x .312L	2
A10102-8	Nut, 10-32 Hex	1
C 4508-5	IC Socket, 16 Pin	1
C 6821-0	Edge Card Connector, 22 Contact	1
C 7500-9	#10 Flanged Spade	1
C 7705-4	Flat Cable Clamp	1
C 8812-7	5.5" Cable Tie	2
C10060-9	Header, 5 Pin R Angle Locking	1
C10184-7	Dual Binding Post	2
F11160-3	Strain Relief, Pwr Cord (U.S. Models)	1
C10187-0	Strain Relief, Pwr Cord (European Models)	1
F12672-6	Back Panel	1
P10286-6	Board, PIP Interconnect	1

Chassis Front Assembly

CPN	ITEM	QTY
A10086-10824	Screw, 8-32 x 1.50 RDHD PH (for handles)	4
C10258-9	Screw, 6-32 x .75 FLTHD	2
D 6013-3	Pushbutton, .75 Beaded	1
D 8048J6	Handle	2
D 8049J4	Panel Cap	2
F12647-8	Panel Cap Spacer	2
D 8052J8	End Cap	2
A10101-12	Spacer, #8 x 5/16OD x 1/4L	2
A10101-5	Nylon Washer, .5 x .136 x .02	2
A10103-10816	Screw, #8 x 1.00 Flat HD	2
A10173-1	Clip, Filter Grille	2
B 5796-6	Velcro Tape, 1/2 x 1/4	8
D 7696-4	Filter, FR Foam .53 x 16.7	2
D 8752-4	Grille Extrusion	1

Note: Old style grills with the one piece filter behind the grill are no longer available. If an old amplifier needs a new grill, the only option is to convert it to the new style by ordering part number M46504-3, which includes the bottom cover. New grills will not fit onto old bottom covers.

Parts List (Non-Module)

Chassis Front Assembly (Cont.)

CPN	ITEM	QTY
A10086-10604	Screw, 6-32 x .25	3
C 6005-0	Set Screw, 6-32 x .18 cup point (for knobs)	2
D 4108-3	Collar, .35 Round (for pushbutton switch)	1
D 6265-9	Knob	2
D 7937-2	Collar, LED Plastic Silver	5
D 8694J7	Front Panel	1
F11322-9	Overlay, MA-2400 FP	1

Main Chassis Assembly

CPN	ITEM	QTY
A10094-3	Washer, Black #6 Int Star	19
A10110-70605	Screw, 6-32 x .312 Taptite	16
C 6965-5	Screw, 6-32 x .156	4
D 8501-5	Top Cover	1
A10091-10406	Screw, 4-40 x .37 Flat Head	2
A10092-10607	Screw, 6-32 x .437 Socket Head	3
A10094-4	Washer, #6 Int Star, Zinc	3
A10094-6	Washer, #8 Int Star	4
F12609-8	Bottom Cover	1
A10109-10822	Screw, 8-18 x 1.375	2
A10110-70812	Screw, 8-32 x .750 Taptite	2
A10192-1	Snap bushing, .500	4
C 1811-6	4" Cable Tie	4
C 1813-2	7.5" Cable Tie & Clamp	2
C 3163-0	Solder Lug, #6 Hole	1
C 6709-7	Ferrite Bead	4
C 6912-7	Tension Retaining Board Supports	2
C 6913-5	1" Spacer Toggle Nut, Plastic	2
C 6914-3	.75" Spacer Toggle Nut, Plastic	2
C 6918-4	1" Cable Tie Mount, Adhesive Back	1
C 7265-9	Screw, #2 x 3/8 Sheet Metal	2
C 7351-7	Connector, 10-12 GA Splice	1
C 9091-7	Power Switch, 10A Push Button, SPST	1
C 7134-7	Micro Switch --Power Switch for Older Amplifiers	1
D 7167-6	Plunger --Used with above Micro Switch	1
C 9491-9	Screw, 6-32 x .312	10
C 9592-4	Capacitor, .01uF 250V Film	1
C 9953-8	Screw, 6-20 x .312	6
D 7217-9	Insulator, .031 x 1.68 x 1.78 Fiberboard	2
D 7784-8	Voltage Gain Label	1
D 8251-7	Fuse Replacement Label	1
D 8854-8	Jumper, Output Ground to Chassis	1
H43424-3	.75 x 3.5 Slit Tube	2
C 7062-0	Screw, 6-32 x 5/16 Flathead (Fan Bracket)	2
C 9938-9	Fan Blade	1
D 8439-8	Fan Bracket	1

Module and Schematic Information

Module History

Since the introduction of the MA-2400 amplifier there have been several updates and revisions. Some of these changes called for new modules. The following is a list of modules used up to this date, March 1996.

Output Modules: (left and right are identical)

Q42670-2

Original output module on P10233-8.

Q42887-2

Output module on P10315-3 board. No longer available. Use Q43065-4 as service replacement.

Q42985-4

Output module on P10337-7 board. No longer available. Use Q43358-3 as service replacement.

Q43194-2

Output module on P10396-3 board.

Q43358-3

Output module on P10433-4 board.

Main Modules:

Q42667-8

Main module on D 6978-7 board. No longer available. Use Q42777-5 as service replacement.

Q42737-9

Main module on D 6978-7 board. No longer available. Use Q42777-5 as service replacement.

Q42753-6

Main module on D 7150-2 board. No longer available. Use Q42777-5 as service replacement.

Q42777-5

Main module on D 7251-8 board. Used as a replacement for all older modules.

Q42982-1

Main module on D 7911-7 board. No longer available use Q43257-7 as service replacement.

Q43037-3

Main module on D 7993-5 board. No longer available use Q43257-7 as service replacement.

Q43132-2

Main module on D 8283-0 board.

Q43272-6

Main module on D 8283-0 board.

Q43257-7

Main module on D 8369-7 board.

Fuse Module:

Q42742-9

Fuse module on P10202-3 Board.

M44161-4

Fuse module on P10387-2 board.

Display Module:

Q42742-9

Display module on D 6260C4 board.

Q42875-7

Display module on D 6260C4 board.

Q43442-5

Display module on D 8897-7 board.

Schematic Information

The schematics provided are representative only. There may be slight variations between amplifier to amplifier. These schematics are intended to be used for troubleshooting purposes only.

For amplifiers with main boards D 6978-7, D 7150-2, or D 7251-8 refer to schematic numbers J0342-6, J0262-6, and display schematic J0242-8.

For amplifiers with main boards D 7605-5, or D 7911-7 refer to schematic number J0449-9.

For amplifiers with main boards D 7993-5, or D 8283-0 refer to schematic number J0531-4.

For amplifiers with a main board D 8369-7, refer to schematic number J0625-4.

Fuse Module Parts Lists

Q42742-9 Fuse Module

C1, C2	C 5234-7	.047μF 125V
D1, D2	C 3181-2	1N4148 Diode
0 Ohm	C 5868-2	.25W Jumper
R1, R2	A10266-1001	10 Ohm .25W
K1, K2	C 7823-5 C 7890-4	24V, 30A Relay Relay Cap
F1	C 5060-6	Fuse Mount Clips
Cable	H42918-5	3-Cond. W/Conn.
Board	P10202-3	

M44161-4 Fuse Module

C1, C2	C 5234-7	.047μF 125V
D1, D2	C 3181-2	1N4148 Diode
R1, R2	A10266-1001	10 Ohm .25W
K1, K2	C 7891-2	30A Relay
F1	C 5060-6	Fuse Mount Clips
Tabs	C 7817-7	Faston, PC Mount
Cable	H42918-5	3-Cond. W/Conn
Board	P10387-2	

Note: F1 Fuse is not included on Module Assemblies.
Please See Power Supply Parts List for fuse Part Number.

Q42742-9 Display Module (D 6260C4 board) Parts List

Capacitors

C501	C601	C 6802-0	.47μF Ax 50V
C502	C602	C 6806-1	.01μF Ax 100V
C503	C603	C 6806-1	.01μF Ax 100V
C504	C604	C 7353-3	.22μF Ax 50V
C505	C605	C 5050-7	4.7μF Ax 100V Lytic
C507	C607	C 6809-5	220pF Ax 100V
C508	C608	C 6807-9	.001μF Ax 100V
C701		C 6802-0	.47μF Ax 50V
C702		C 6802-0	.47μF Ax 50V

Diodes

D501	D601	C 3181-2	1N4148
D502	D602	C 3181-2	1N4148
D503	D603	C 3181-2	1N4148
D504	D604	D 7378-9	1N966B Lo Noise
D701		C 3533-4	1N966B 16V Zener
D702		C 3533-4	1N966B 16V Zener

LEDs

E501	E601	C 7863-1	Grn SPI/IOC
E502	E602	C 4342-9	Amber ODEP
E701		C 4342-9	Amber Enable

Transistors

Q501	Q601	C 3625-8	PNP 2N4125
Q502	Q602	D 2961-7	NPN 2N3859A Sel
Q503	Q603	D 2961-7	NPN 2N3859A Sel
Q504	Q604	C 3625-8	PNP 2N4125
Q505	Q605	D 2961-7	NPN 2N3859A Sel
Q506	Q606	C 3954-2	PNP MPSA56

Resistors

R501	R601	A10266-1051	1M
R502	R602	A10266-3331	33K
R503	R603	A10266-2741	270K
R504	R604	A10266-1031	10K
R505	R605	A10266-1022	1K .5W
R506	R606	A10266-2222	2.2K .5W
R507	R607	A10266-1032	20K .5W
R508	R608	A10266-1351	1.3M
R509	R609	A10266-7551	7.5M
R510	R610	A10266-4751	4.7M
R511	R611	A10266-4741	470K
R512	R612	A10266-4731	47K
R513	R613	A10266-1522	1.5K .5W
R514	R614	A10266-1001	10
R515	R615	A10266-3351	3.3M
R516	R616	A10266-4741	470K
R517	R617	A10266-1551	1.5M
R518	R618	A10266-1031	10K

R524	R624	A10266-2221	2.2K
R525	R625	A10266-5631	56K
R701		A10266-1522	1.5K .5W
R702		A10266-5111	510
R703		A10266-2231	22K
R704		A10266-1031	10K
R705		A10266-1031	10K
R706		A10266-2231	22K
R707		A10266-5111	510

ICs

U501	U601	C 4345-2	LM339
U502		C 5070-7	TL072
U503		C 4345-2	LM339

Misc.

Board	D 6260C4	
J3	C 4508-5	16 Pin Header
J10	C 7526-4	3 Pin Header
Spacer	C 4759-7	LED Nylon Spacer

Q42875-7 Display Module (D 6260C4 board) Parts List

Capacitors

C501	C601	C 6802-0	.47μF Ax
C502	C602	C 6806-1	.01μF Ax
C503	C603	C 6806-1	.01μF Ax
C507	C607	C 6809-5	220pF
C701		C 6802-0	.47μF Ax
C702		C 6802-0	.47μF Ax

Diodes

D501	D601	C 3181-2	1N4148
D502	D602	C 3181-2	1N4148
D503	D603	C 3181-2	1N4148
D701		C 3533-4	1N966B 16V Zener
D702		C 3533-4	1N966B 16V Zener

LEDs

E501	E601	C 7863-1	Grn SPI/IOC
E502	E602	C 8740-0	Amber ODEP
E701		C 4342-9	Amber Enable

Transistors

Q501	Q601	C 3625-8	PNP 2N4125
Q502	Q602	D 2961-7	NPN 2N3859A Sel
Q503	Q603	D 2961-7	NPN 2N3859A Sel
Q504	Q604	C 3625-8	PNP 2N4125
Q506	Q606	C 3954-2	PNP MPSA56

Resistors

R501	R601	A10266-1051	1M
R502	R602	A10266-3331	33K
R503	R603	A10266-2741	270K
R504	R604	A10266-1031	10K
R505	R605	A10266-1022	1K .5W
R506	R606	A10266-2222	2.2K .5W
R507	R607	A10266-1032	20K .5W
R508	R608	A10266-1351	1.3M
R509	R609	A10266-7551	7.5M
R510	R610	A10266-4751	4.7M
R511	R611	A10266-4741	470K
R512	R612	A10266-2221	2.2K
R513	R613	A10266-1522	1.5K .5W
R514	R614	A10266-1001	10
R516		A10266-1021	1K
R524	R624	A10266-2221	2.2K
R701		A10266-1522	1.5K .5W
R702		A10266-5111	510
R703		A10266-2231	22K
R704		A10266-1031	10K
R705		A10266-1031	10K
R706		A10266-2231	22K
R707		A10266-5111	510

ICs

U501	U601	C 4345-2	LM339
U502		C 5070-7	TL072

Misc.

Board	D 6260C4	
J3	C 4508-5	16 Pin Header
J10	C 7526-4	3 Pin Header
Spacer	A10101-2	LED Spacer

Q43442-5 Display Module (D 8897-7 board) Parts List

Capacitors

C501	C601	C 6802-0	.47μF Ax
C502	C602	C 6806-1	.01μF Ax
C503	C603	C 6806-1	.01μF Ax
C507	C607	C 6809-5	220pF
C701		C 6804-6	.1μF Ax
C702		C 6804-6	.1μF Ax
C703		C 6804-6	.1μF Ax
C704		C 6804-6	.1μF Ax

Diodes

D501	D601	C 3181-2	1N4148
D502	D602	C 3181-2	1N4148
D503	D603	C 3181-2	1N4148
D701		C 8235-1	1N6263

LEDs

E501	E601	C 7863-1	Grn SPI/IOC
E502	E602	C 4342-9	Amber ODEP
E701		C 4342-9	Amber Enable

Transistors

Q501	Q601	C 3625-8	PNP 2N4125
Q502	Q602	D 2961-7	NPN 2N3859A Sel
Q503	Q603	D 2961-7	NPN 2N3859A Sel
Q504	Q604	C 3625-8	PNP 2N4125
Q505	Q605	C 3954-2	PNP MPSA56

Resistors

R501	R601	A10266-1051	1M
R502	R602	A10266-3331	33K
R503	R603	A10266-2741	270K
R504	R604	A10266-1031	10K
R505	R605	A10266-1022	1K .5W
R506	R606	A10266-2222	2.2K .5W
R507	R607	A10266-2032	20K .5W
R508	R608	A10266-1351	1.3M
R509	R609	A10266-7551	7.5M
R510	R610	A10266-4751	4.7M
R511	R611	A10266-4741	470K
R512	R612	A10266-2221	2.2K
R513	R613	A10266-1522	1.5K .5W
R514	R614	A10266-1001	10
R515	R615	A10266-2221	2.2K
R701		A10266-1522	1.5K .5W
R703		A10266-2031	20K
R704		A10266-1031	10K
R705		A10266-1031	10K
R706		A10266-2031	20K

ICs

U501	U601	C 4345-2	LM339
U502		C 5070-7	TL072
U701		C 8518-0	MC78L15ACP +15V
U702		C 8519-8	MC79L15ACP -15V

Misc.

Board	D 8897-7	
J3	C 8784-8	16 Pin Header
J10	C 7526-4	3 Pin Header
Spacer	A10101-2	LED Spacer

Q42670-2 Output Module (P10233-8 board) Parts List

Capacitors

C01	C 3978-1	.047μF
C02	C 2938-6	.1μF
C03	C 2938-6	.1μF
C04	C 6806-1	.01μF
C05	C 6806-1	.01μF
C06	C 6806-1	.01μF
C07	C 6807-9	.001μF
C08	C 6810-3	180pF
C09	C 6809-5	220pF

Diodes

D01	C 2851-1	1N4004
D02	C 2851-1	1N4004
D03	C 2851-1	1N4004
D04	C 2851-1	1N4004
D05	C 2941-0	1N5402
D06	C 2941-0	1N5402
D07	C 2941-0	1N5402
D08	C 2941-0	1N5402
D09	C 2851-1	1N4004
D10	C 2851-1	1N4004
D11	C 2851-1	1N4004
D12	C 2851-1	1N4004

Inductors

L00	C 6592-6	Output Coil
L01	C 3510-2	470μH
L02	C 3510-2	470μH

Transistors

Q17	C 7271-7	NPN MPSU10
Q19	C 7318-6	PNP MPSU60

Note: Output Transistors, Driver Transistors, Q18, and S100/200 are not included with the module assembly. Refer to the Output Assembly Parts List on pages 17 and 18 for these part numbers.

Resistors

R00	A10266-4711	470
R01	A10266-1011	100
R02	C 7778-1	5.6 .5W Flame Proof
R03	D 6486-2	.2 5W
R04	D 6486-2	.2 5W
R05	D 6486-2	.2 5W
R06	D 6486-2	.2 5W
R07	D 6486-2	.2 5W
R08	D 6486-2	.2 5W
R09	C 7779-9	22 .5W Flame Proof
R10	A10266-1011	100
R11	C 7317-8	2.7 5W
R12	A10266-2R73	2.7 1W
R13	A10266-4711	470
R14	A10266-2R73	2.7 1W
R15	D 6486-2	.2 5W
R16	D 6486-2	.2 5W
R17	D 6486-2	.2 5W
R18	D 6486-2	.2 5W
R19	D 6486-2	.2 5W
R20	D 6486-2	.2 5W
R21	C 7778-1	5.6 .5W Flame Proof
R22	C 7779-9	22 .5W Flame Proof
R23	C 6844-2	250 Pot LS
R24	A10266-1331	13K
R25	A10266-2221	2.2K
R26	C 6844-2	250 Pot HS
R27	A10266-3911	390
R28	A10266-1331	13K
R29	A10266-5101	51
R30*	A10265-10201*	102*

Misc.

Board	P10233-8	
Jumpers	C 5868-2	0 Ohm (Qty 5)
J500 J600	C 7057-0	10 Pin Header

*Note: R30 is 102 Ohms in most units, though in some cases a different value may be used to match the installed S100/S200 LM334 (C5826-0) device grade. This is the standard value and is used with the most common LM334 grade, green. If the LM334 is marked with a blue dot, R30 should be a 107 Ohm resistor (A10265-10701); if it is marked with a yellow dot then R30 should be a 100 Ohm resistor (A10265-10001).

Q42887-2 Output Module (P10315-3 board) Parts List

Capacitors

C01	C 8511-5	.047μF
C02	C 8426-6	.1μF
C03	C 8426-6	.1μF
C04	C 6806-1	.01μF
C05	C 6806-1	.01μF
C06	C 6806-1	.01μF
C07	C 6807-9	.001μF
C08	C 6810-3	180pF
C09	C 6809-5	220pF
C43	C 7697-3	.01μF

Diodes

D01	C 2851-1	1N4004
D02	C 2851-1	1N4004
D03	C 2851-1	1N4004
D04	C 2851-1	1N4004
D05	C 2941-0	1N5402
D06	C 2941-0	1N5402
D07	C 2941-0	1N5402
D08	C 2941-0	1N5402
D09	C 2851-1	1N4004
D10	C 2851-1	1N4004
D11	C 2851-1	1N4004
D12	C 2851-1	1N4004

Inductors

L00	C 6592-6	Output Coil
L01	C 3510-2	470μH
L02	C 3510-2	470μH

Transistors

Q17	C 8508-1	NPN 2SC3298B
Q19	C 8509-9	PNP 2SA1306B

Note: Output Transistors, Driver Transistors, Q18, and S100/200 are not included with the module assembly. Refer to the Output Assembly Parts List on pages 17 and 18 for these part numbers.

Resistors

R00	A10266-4711	470
R01	A10266-1011	100
R02	C 7778-1	5.6 .5W Flame Proof
R03	D 6486-2	.2 5W
R04	D 6486-2	.2 5W
R05	D 6486-2	.2 5W
R06	D 6486-2	.2 5W
R07	D 6486-2	.2 5W
R08	D 6486-2	.2 5W
R09	C 7779-9	22 .5W Flame Proof
R10	A10266-1011	100
R11	C 7317-8	2.7 5W
R12	A10266-2R73	2.7 1W
R13	A10266-4711	470
R14	A10266-2R73	2.7 1W
R15	D 6486-2	.2 5W
R16	D 6486-2	.2 5W
R17	D 6486-2	.2 5W
R18	D 6486-2	.2 5W
R19	D 6486-2	.2 5W
R20	D 6486-2	.2 5W
R21	C 7778-1	5.6 .5W Flame Proof
R22	C 7779-9	22 .5W Flame Proof
R23	C 6844-2	250 Pot LS
R24	A10266-1331	13K
R25	A10266-2221	2.2K
R26	C 6844-2	250 Pot HS
R27	A10266-3911	390
R28	A10266-1331	13K
R29	A10266-5101	51
R30*	A10265-10201*	102*

Misc.

Board	P10315-3	
Jumpers	C 5868-2	0 Ohm (Qty 6)
Clips	D 6414-3	Q17/Q19
J500 J600	C 7057-0	10 Pin Header

*Note: R30 is 102 Ohms in most units, though in some cases a different value may be used to match the installed S100/S200 LM334 (C5826-0) device grade. This is the standard value and is used with the most common LM334 grade, green. If the LM334 is marked with a blue dot, R30 should be a 107 Ohm resistor (A10265-10701); if it is marked with a yellow dot then R30 should be a 100 Ohm resistor (A10265-10001).

Q42985-4 Output Module (P10337-7 board) Parts List

Capacitors

C01	C 8511-5	.047μF 250V Ax
C02	C 8426-6	.1μF
C03	C 8426-6	.1μF
C04	C 6806-1	.01μF 100V Ax
C05	C 6806-1	.01μF 100V Ax
C06	C 6806-1	.01μF 100V Ax
C07	C 6807-9	.001μF 100V Ax
C08	C 6810-3	180pF
C09	C 6809-5	220pF
C43	C 7697-3	.01μF Disc

Diodes

D01	C 2851-1	1N4004
D02	C 2851-1	1N4004
D03	C 2851-1	1N4004
D04	C 2851-1	1N4004
D05	C 2941-0	1N5402
D06	C 2941-0	1N5402
D07	C 2941-0	1N5402
D08	C 2941-0	1N5402
D09	C 2851-1	1N4004
D10	C 2851-1	1N4004
D11	C 2851-1	1N4004
D12	C 2851-1	1N4004

Inductors

L00	C 6592-6	1.3μH Output Coil
L01	C 3510-2	470μH
L02	C 3510-2	470μH

Transistors

Q17	C 8508-1	NPN 2SC3298B
Q19	C 8509-9	PNP 2SA1306B

Note: Output Transistors, Driver Transistors, Q18, and S100/200 are not included with the module assembly. Refer to the Output Assembly Parts List on pages 17 and 18 for these part numbers.

Resistors

R00	A10266-7501	75
R01	A10266-1011	100
R02	C 7778-1	5.6 .5W Flame Proof
R03	C 6486-2	.2 5W
R04	C 6486-2	.2 5W
R05	C 6486-2	.2 5W
R06	C 6486-2	.2 5W
R07	C 6486-2	.2 5W
R08	C 6486-2	.2 5W
R09	C 7779-9	22 .5W Flame Proof
R10	A10266-1011	100
R11	C 7317-8	2.7 5W
R12	A10266-2R73	2.7 1W
R13	A10266-7501	75
R14	A10266-2R73	2.7 1W
R15	C 6486-2	.2 5W
R16	C 6486-2	.2 5W
R17	C 6486-2	.2 5W
R18	C 6486-2	.2 5W
R19	C 6486-2	.2 5W
R20	C 6486-2	.2 5W
R21	C 7778-1	5.6 .5W Flame Proof
R22	C 7779-9	22 .5W Flame Proof
R23	C 6844-2	250 Pot LS Bias
R24	A10266-1331	13K
R25	A10266-2221	2.2K
R26	C 6844-2	250 Pot HS Bias
R27	A10266-3911	390
R28	A10266-1331	13K
R29	A10266-5101	51
R30*	A10265-10201*	102* 1%

Misc.

Board	P10337-7	
Z1-Z9	C 5868-2	0 Ohm Jumper
Clips	D 6414-3	Q17/Q19 Hold Down
J500 J600	C 7057-0	10 Pin Header

*Note: R30 is 102 Ohms in most units, though in some cases a different value may be used to match the installed S100/S200 LM334 (C5826-0) device grade. This is the standard value and is used with the most common LM334 grade, green. If the LM334 is marked with a blue dot, R30 should be a 107 Ohm resistor (A10265-10701); if it is marked with a yellow dot then R30 should be a 100 Ohm resistor (A10265-10001).

Q43194-2 Output Module (P10396-3 board) Parts List

Capacitors

C01	C 8511-5	.047μF 250V Ax
C02	C 8426-6	.1μF
C03	C 8426-6	.1μF
C04	C 6806-1	.01μF 100V Ax
C05	C 6806-1	.01μF 100V Ax
C06	C 6806-1	.01μF 100V Ax
C07	C 6807-9	.001μF 100V Ax
C08	C 6810-3	180pF
C09	C 6809-5	220pF
C43	C 7697-3	.01μF Disc

Diodes

D01	C 2851-1	1N4004
D02	C 2851-1	1N4004
D03	C 2851-1	1N4004
D04	C 2851-1	1N4004
D05	C 2941-0	1N5402
D06	C 2941-0	1N5402
D07	C 2941-0	1N5402
D08	C 2941-0	1N5402
D09	C 2851-1	1N4004
D10	C 2851-1	1N4004
D11	C 2851-1	1N4004
D12	C 2851-1	1N4004

Inductors

L00	C 6592-6	1.3μH Output Coil
L01	C 3510-2	470μH
L02	C 3510-2	470μH

Transistors

Q17	C 8508-1	NPN 2SC3298B
Q19	C 8509-9	PNP 2SA1306B

Note: Output Transistors, Driver Transistors, Q18, and S100/200 are not included with the module assembly. Refer to the Output Assembly Parts List on pages 17 and 18 for these part numbers.

Resistors

R00	A10266-7501	75
R01	A10266-1011	100
R02	C 7778-1	5.6 .5W Flame Proof
R03	C 6486-2	.2 5W
R04	C 6486-2	.2 5W
R05	C 6486-2	.2 5W
R06	C 6486-2	.2 5W
R07	C 6486-2	.2 5W
R08	C 6486-2	.2 5W
R09	C 7779-9	22 .5W Flame Proof
R10	A10266-1011	100
R11	C 7317-8	2.7 5W
R12	A10266-2R73	2.7 1W
R13	A10266-7501	75
R14	A10266-2R73	2.7 1W
R15	C 6486-2	.2 5W
R16	C 6486-2	.2 5W
R17	C 6486-2	.2 5W
R18	C 6486-2	.2 5W
R19	C 6486-2	.2 5W
R20	C 6486-2	.2 5W
R21	C 7778-1	5.6 .5W Flame Proof
R22	C 7779-9	22 .5W Flame Proof
R23	C 6844-2	250 Pot LS Bias
R24	A10266-1331	13K
R25	A10266-2221	2.2K
R26	C 6844-2	250 Pot HS Bias
R27	A10266-3911	390
R28	A10266-1331	13K
R29	A10266-5101	51
R30*	A10265-10201*	102* 1%

Misc.

Board	P10396-3	
Z1-Z7, Z9	C 5868-2	0 Ohm Jumper
Z8	A10124-24	Solid Wire
Clips	D 6414-3	Q17/Q19 Hold Down
J500 J600	C 7057-0	10 Pin Header

*Note: R30 is 102 Ohms in most units, though in some cases a different value may be used to match the installed S100/S200 LM334 (C5826-0) device grade. This is the standard value and is used with the most common LM334 grade, green. If the LM334 is marked with a blue dot, R30 should be a 107 Ohm resistor (A10265-10701); if it is marked with a yellow dot then R30 should be a 100 Ohm resistor (A10265-10001).

Q43358-3 Output Module (P10433-4 board) Parts List

Capacitors

C01	A10434-437JD	.047μF 250V
C02	C 8426-6	.1μF
C03	C 8426-6	.1μF
C04	C 6806-1	.01μF 100V Ax
C05	C 6806-1	.01μF 100V Ax
C06	C 6806-1	.01μF 100V Ax
C07	C 6807-9	.001μF 100V Ax
C08	C 6810-3	180pF
C09	C 6809-5	220pF
C43	C 7697-3	.01μF Disc

Diodes

D01	C 2851-1	1N4004
D02	C 2851-1	1N4004
D03	C 2851-1	1N4004
D04	C 2851-1	1N4004
D05	C 2941-0	1N5402
D06	C 2941-0	1N5402
D07	C 2941-0	1N5402
D08	C 2941-0	1N5402
D09	C 2851-1	1N4004
D10	C 2851-1	1N4004
D11	C 2851-1	1N4004
D12	C 2851-1	1N4004

Inductors

L00	C 6592-6	1.3μH Output Coil
L01	C 3510-2	470μH
L02	C 3510-2	470μH

Transistors

Q17	C 8508-1	NPN 2SC3298B
Q19	C 8509-9	PNP 2SA1306B

Note: Output Transistors, Driver Transistors, Q18, and S100/200 are not included with the module assembly. Refer to the Output Assembly Parts List on pages 17 and 18 for these part numbers.

Resistors

R00	A10266-7501	75
R01	A10266-1011	100
R02	C 7778-1	5.6 .5W Flame Proof
R03	C 6486-2	.2 5W
R04	C 6486-2	.2 5W
R05	C 6486-2	.2 5W
R06	C 6486-2	.2 5W
R07	C 6486-2	.2 5W
R08	C 6486-2	.2 5W
R09	C 7779-9	22 .5W Flame Proof
R10	A10266-1011	100
R11	C 7317-8	2.7 5W
R12	A10266-2R74	2.7 2W
R13	A10266-7501	75
R14	A10266-2R74	2.7 2W
R15	C 6486-2	.2 5W
R16	C 6486-2	.2 5W
R17	C 6486-2	.2 5W
R18	C 6486-2	.2 5W
R19	C 6486-2	.2 5W
R20	C 6486-2	.2 5W
R21	C 7778-1	5.6 .5W Flame Proof
R22	C 7779-9	22 .5W Flame Proof
R23	C 6844-2	250 Pot LS Bias
R24	A10266-1331	13K
R25	A10266-2221	2.2K
R26	C 6844-2	250 Pot HS Bias
R27	A10266-3911	390
R28	A10266-1331	13K
R29	A10266-5101	51
R30	A10265-10201	102 1%
R41	A10266-5R61	5.6
R42	A10266-5R61	5.6
R43	A10266-5R61	5.6
R44	A10266-5R61	5.6
R45	A10266-5R61	5.6
R46	A10266-5R61	5.6

Misc.

Board	P10433-4	
Z1-Z7, Z9-Z12	C 5868-2	0 Ohm Jumper
Z8	A10124-24	Solid Wire
Clips	D 6414-3	Q17/Q19 Hold Down
P500 P600	C 7057-0	10 Pin Header

Q42667-8 Main Module (D 6978-7 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C3	C 4303-1	1000μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 6094-9	33μF
C100	C200 C 5053-1	18μF
C101	C201 C 2821-4	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6804-6	.1μF
C105	C205 C 6950-7	82pF
C106	C206 C 6950-7	82pF
C108	C208 C 6812-9	47pF
C112	C212 C 6803-8	.12μF
C113	C213 C 6802-0	.47μF
C114	C214 C 3729-8	100μF
C115	C215 C 3729-8	100μF
C116	C216 C 6802-0	.47μF
C117	C217 C 6803-8	.12μF
C118	C218 C 6812-9	47pF
C122	C222 C 6811-1	100pF
C124	C224 C 6809-5	220pF
C125	C225 C 3729-8	100μF
C127	C227 C 3729-8	100μF
C128	C228 C 5243-8	.1μF
C130	C230 C 6813-7	27pF
C133	C233 C 2821-4	10pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6814-5	12pF
C139	C239 C 6814-5	12pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 5362-6	2.2μF
C145	C245 C 6814-5	12pF
C146	C246 C 6809-5	220pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C 149	C249 C 6808-7	470pF
C152	C252 C 6809-5	220pF
C153	C253 C 6804-6	.1μF

Diodes

D1	C 2851-1	1N4004
D2	C 2851-1	1N4004
D3	C 2851-1	1N4004
D4	C 2851-1	1N4004
D5	C 2851-1	1N4004

D6	C 2851-1	1N4004
D7	C 2851-1	1N4004
D104	D204 C 2851-1	1N4004
D105	D205 C 2851-1	1N4004
D106	D206 C 2851-1	1N4004
D107	D207 C 2851-1	1N4004
D108	D208 C 3181-2	1N4148
D109	D209 C 3181-2	1N4148
D110	D210 C 3181-2	1N4148
D111	D211 C 3181-2	1N4148
D112	D212 C 3181-2	1N4148
D113	D213 C 3181-2	1N4148
D114	D214 C 3181-2	1N4148
D115	D215 C 3181-2	1N4148
D120	D220 C 3181-2	1N4148
D121	D221 C 3181-2	1N4148
D122	D222 C 3181-2	1N4148
D123	D223 C 5061-4	1N3070

Resistor Networks

N100	N200	D 4669-4	Balanced Input
N101	N201	D 6081-0	Resistor Network-B
N102	N202	D 6082-8	Resistor Network-C

Transistors

Q100	Q200	D 2961-7	SEL 2N3859A
Q101	Q201	C 3578-9	MP5A93
Q102	Q202	C 3810-6	MP5A43/A42
Q103	Q203	C 3786-8	PN4250A
Q104	Q204	C 3625-8	2N4125
Q105	Q205	C 3578-9	MP5A93
Q106	Q206	C 3625-8	2N4125
Q107	Q207	C 3786-8	PN4250A
Q108	Q208	D 2961-7	SEL 2N3859A
Q109	Q209	D 2961-7	SEL 2N3859A
Q110	Q210	C 3810-6	MP5A43/A42
Q111	Q211	D 2961-7	SEL 2N3859A
Q112	Q212	C 3625-8	2N4125
Q113	Q213	C 3625-8	2N4125
Q115	Q215	D 2962-5	MPS8097/MP5A18
Q116	Q216	C 3786-8	PN4250A
Q117	Q217	D 2961-7	SEL 2N3859A
Q118	Q218	D 2961-7	SEL 2N3859A
Q119	Q219	C 3625-8	2N4125
Q120	Q220	C 3625-8	2N4125

Resistors

R1	A10265-53621	53.6K
R2	A10266-2402	24 OHM
R3	A10266-2402	24 OHM
R4	A10265-46421	46.4K

Q42667-8 Main Module (D 6978-7 board) Parts List Cont.

R11		A10266-5621	5.6K	R154	R254	C 7782-3	100 Ohm
R12		A10266-4331	43K	R156	R256	A10266-1321	1.3K
R13		A10266-1021	1K	R157	R257	A10266-1321	1.3K
R14		A10266-8221	8.2K	R158	R258	A10266-9121	9.1K
R15		A10266-6211	620 Ohm	R159	R259	A10266-1031	10K
R100	R200	C 7592-6	Header	R161	R261	A10266-4701	47 Ohm
R101	R201	A10265-49911	4.99K	R162	R262	A10266-4701	47 Ohm
R102	R202	A10266-1021	1K	R165	R265	A10265-53611	5.36K
R103	R203	A10266-1041	100K	R167	R267	A10266-1021	1K
R104	R204	A10266-2721	2.7K	R168	R268	A10265-95301	953 Ohm
R105	R205	A10266-2721	2.7K	R170	R270	A10266-1021	1K
R106	R206	A10266-1231	12K	R171	R271	A10265-95301	953 Ohm
R107	R207	A10266-4731	47K	R174	R274	A10265-38311	3.83K
R108	R208	A10266-8211	820 Ohm	R175	R275	A10265-11811	1.18K
R109	R209	A10266-6801	68 Ohm	R176	R276	A10266-1041	100K
R110	R210	A10266-4731	47K	R177	R277	C 5062-2	100K Pot
R113	R213	A10266-4721	4.7K	R178	R278	A10266-1231	12K
R114	R214	A10266-4721	4.7K	R179	R279	A10266-4731	47K
R115	R215	A10266-5141	510K	R180	R280	A10266-4711	470 Ohm
R116	R216	A10266-3351	3.3M	R181	R281	A10266-4721	4.7K
R118	R218	A10266-2711	270 Ohm	R182	R282	A10266-2201	22 Ohm
R119	R219	A10266-3911	390 Ohm	R183	R283	A10266-2421	2.4K
R120	R220	A10266-2711	270 Ohm	R185	R285	A10266-2421	2.4K
R121	R221	C 5062-2	100K Pot	R186	R286	A10266-1051	1M
R122	R222	A10266-2741	270K	Switches			
R123	R223	A10266-2731	27K	S2		C 7325-1	DPDT, Gnd Lift
R124	R224	A10266-6821	6.8K	S3		C 7363-2	DPDT, Sensitivity
R125	R225	C 7782-3	100 Ohm	S100		C 6781-6	6P3T, St/Mono
R126	R226	C 7782-3	100 Ohm	IC's			
R127	R227	A10266-6821	6.8K	U1		C 5095-2	MC7815
R128	R228	A10266-1031	10K	U2		C 5096-0	MC7915
R129	R229	A10266-1041	100K	U100	U200	C 6500-0	UPA77 PNP
R130	R230	A10266-1041	100K	U103	U203	C 6910-1	UPA76 NPN
R131	R231	A10266-1031	10K	U104	U204	C 6900-2	MC34084P
R132	R232	C 5062-2	100K Pot	Connectors			
R133	R233	A10266-2741	270K	J9		C 6871-5	Header, 6 Pin
R134	R234	A10266-2731	27K	J10		C 6850-9	Header, 4 Pin
R135	R235	C 7782-3	100 Ohm	J11		C 7077-8	Retainer, 3 Pin
R136	R236	A10266-6821	6.8K	J100	J200	C 6777-4	Phone Jack
R137	R237	C 7782-3	100 Ohm	J500	J800	D 6619-7	10" Ribbon Assy
R138	R238	A10266-6821	6.8K	J600	J700	D 6620-5	6" Ribbon Assy
R139	R239	A10266-8211	820 Ohm				
R140	R240	A10266-6801	68 Ohm				
R141	R241	A10266-1541	150K				
R142	R242	A10266-1541	150K				
R146	R246	A10266-1031	10K				
R147	R247	C 7781-5	200 Ohm				
R148	R248	A10266-2721	2.7K				
R149	R249	C 7781-5	200 Ohm				
R150	R250	A10266-2721	2.7K				
R151	R251	A10266-1031	10K				
R152	R252	A10266-1231	12K				

Q42667-8 Main Module (D 6978-7 board) Parts List Cont.

Misc.

Mounts U1, U2:

(2)	C 1889-2	6-32 Nut
(2)	C 2176-3	6-32 X .5 Screw
(2)	C 5341-0	Heatsink
(2)	C 5594-4	Star Washer

Mounts U104, U204:

(2)	C 3450-1	14 Pin Socket
-----	----------	---------------

Covers For J100, J200:

(2)	C 6778-2	Cover, Phone Jk
-----	----------	-----------------

Circuit Board: D 6978-7

Q42737-9 Main Module (D 6978-7 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C3	C 4303-1	1000μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 6094-9	33μF
C100	C200 C 5053-1	18μF
C101	C201 C 2821-4	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6804-6	.1μF
C105	C205 C 6950-7	82pF
C106	C206 C 6950-7	82pF
C108	C208 C 6812-9	47pF
C112	C212 C 6803-8	.12μF
C113	C213 C 6802-0	.47μF
C114	C214 C 3729-8	100μF
C115	C215 C 3729-8	100μF
C116	C216 C 6802-0	.47μF
C117	C217 C 6803-8	.12μF
C118	C218 C 6812-9	47pF
C122	C222 C 6811-1	100pF
C124	C224 C 6809-5	220pF
C125	C225 C 3729-8	100μF
C127	C227 C 3729-8	100μF
C128	C228 C 5243-8	.1μF
C130	C230 C 6814-5	12pF
C133	C233 C 2821-4	10pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6814-5	12pF
C139	C239 C 6814-5	12pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 5362-6	2.2μF
C145	C245 C 6814-5	12pF
C146	C246 C 6809-5	220pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C 149	C249 C 6808-7	470pF
C152	C252 C 6809-5	220pF
C153	C253 C 6804-6	.1μF

Diodes

D1	C 2851-1	1N4004
D2	C 2851-1	1N4004
D3	C 2851-1	1N4004
D4	C 2851-1	1N4004
D5	C 2851-1	1N4004

D6	C 2851-1	1N4004
D7	C 2851-1	1N4004
D8	C 3181-2	1N4148
D9	C 3549-0	1N961B
D104	D204 C 2851-1	1N4004
D105	D205 C 2851-1	1N4004
D106	D206 C 2851-1	1N4004
D107	D207 C 2851-1	1N4004
D108	D208 C 3181-2	1N4148
D109	D209 C 3181-2	1N4148
D110	D210 C 3181-2	1N4148
D111	D211 C 3181-2	1N4148
D112	D212 C 3181-2	1N4148
D113	D213 C 3181-2	1N4148
D114	D214 C 3181-2	1N4148
D115	D215 C 3181-2	1N4148
D120	D220 C 3181-2	1N4148
D121	D221 C 3181-2	1N4148
D122	D222 C 3181-2	1N4148
D123	D223 C 5061-4	1N3070
D124	D224 C 5061-4	1N3070

Resistor Networks

N100	N200	D 4669-4	Balanced Input
N101	N201	D 6081-0	Resistor Network-B
N102	N202	D 6082-8	Resistor Network-C

Transistors

Q1	C 7458-0	2N4123
Q2	C 3625-8	2N4125
Q100	Q200 D 2961-7	SEL 2N3859A
Q101	Q201 C 3578-9	MPSA93
Q102	Q202 C 3810-6	MPSA43/A42
Q103	Q203 C 3786-8	PN4250A
Q104	Q204 C 3625-8	2N4125
Q105	Q205 C 3578-9	MPSA93
Q106	Q206 C 3625-8	2N4125
Q107	Q207 C 3786-8	PN4250A
Q108	Q208 D 2961-7	SEL 2N3859A
Q109	Q209 D 2961-7	SEL 2N3859A
Q110	Q210 C 3810-6	MPSA43/A42
Q111	Q211 D 2961-7	SEL 2N3859A
Q112	Q212 C 3625-8	2N4125
Q113	Q213 C 3625-8	2N4125
Q115	Q215 D 2962-5	MPS8097/MPSA18
Q116	Q216 C 3786-8	PN4250A
Q117	Q217 D 2961-7	SEL 2N3859A
Q118	Q218 D 2961-7	SEL 2N3859A
Q119	Q219 C 3625-8	2N4125
Q120	Q220 C 3625-8	2N4125
Q121	Q221 C 7458-0	2N4123
Q122	Q222 C 7458-0	2N4123

Q42737-9 Main Module (D 6978-7 board) Parts List Cont.

Resistors

R1	A10265-53621	53.6K
R2	A10266-2402	24 OHM
R3	A10266-2402	24 OHM
R4	A10265-46421	46.4K
R11	A10266-5621	5.6K
R12	A10266-4331	43K
R13	A10266-1021	1K
R14	A10266-8221	8.2K
R15	A10266-6211	620 Ohm
R100	R200 C 7592-6	Header
R101	R201 A10265-49911	4.99K
R102	R202 A10266-1021	1K
R103	R203 A10266-1041	100K
R104	R204 A10266-2721	2.7K
R105	R205 A10266-2721	2.7K
R106	R206 A10266-1231	12K
R107	R207 A10266-4731	47K
R108	R208 A10266-8211	820 Ohm
R109	R209 A10266-6801	68 Ohm
R110	R210 A10266-4731	47K
R111	R211 A10266-1231	12K
R112	R212 A10266-5131	51K
R113	R213 A10266-4721	4.7K
R114	R214 A10266-4721	4.7K
R115	R215 A10266-5141	510K
R116	R216 A10266-3351	3.3M
R117	R217 A10266-4731	47K
R118	R218 A10266-2711	270 Ohm
R119	R219 A10266-3911	390 Ohm
R120	R220 A10266-2711	270 Ohm
R121	R221 C 5062-2	100K Pot
R122	R222 A10266-2741	270K
R123	R223 A10266-2731	27K
R124	R224 A10266-6821	6.8K
R125	R225 C 7782-3	100 Ohm
R126	R226 C 7782-3	100 Ohm
R127	R227 A10266-6821	6.8K
R128	R228 A10266-1031	10K
R129	R229 A10266-1041	100K
R130	R230 A10266-1041	100K
R131	R231 A10266-1031	10K
R132	R232 C 5062-2	100K Pot
R133	R233 A10266-2741	270K
R134	R234 A10266-2731	27K
R135	R235 C 7782-3	100 Ohm
R136	R236 A10266-6821	6.8K
R137	R237 C 7782-3	100 Ohm
R138	R238 A10266-6821	6.8K
R139	R239 A10266-8211	820 Ohm
R140	R240 A10266-6801	68 Ohm
R141	R241 A10266-1541	150K

R142	R242	A10266-1541	150K
R146	R246	A10266-1031	10K
R147	R247	C 7781-5	200 Ohm
R148	R248	A10266-2721	2.7K
R149	R249	C 7781-5	200 Ohm
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1031	10K
R152	R252	A10266-1231	12K
R154	R254	C 7782-3	100 Ohm
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10266-9121	9.1K
R159	R259	A10266-1031	10K
R161	R261	A10266-4701	47 Ohm
R162	R262	A10266-4701	47 Ohm
R165	R265	A10265-53611	5.36K
R167	R267	A10266-1021	1K
R168	R268	A10265-95301	953 Ohm
R170	R270	A10266-1021	1K
R171	R271	A10265-95301	953 Ohm
R174	R274	A10265-38311	3.83K
R175	R275	A10265-11811	1.18K
R176	R276	A10266-1041	100K
R177	R277	C 5062-2	100K Pot
R178	R278	A10266-1231	12K
R179	R279	A10266-4731	47K
R180	R280	A10266-4711	470 Ohm
R181	R281	A10266-4721	4.7K
R182	R282	A10266-2201	22 Ohm
R183	R283	A10266-2421	2.4K
R185	R285	A10266-2421	2.4K
R186	R286	A10266-1051	1M

Switches

S2	C 7325-1	DPDT, Gnd Lift
S3	C 7363-2	DPDT, Sensitivity
S100	C 6781-6	6P3T, St/Mono

IC's

U1	C 5095-2	MC7815
U2	C 5096-0	MC7915
U100	U200 C 6500-0	UPA77 PNP
U103	U203 C 6910-1	UPA76 NPN
U104	U204 C 6900-2	MC34084P

Q42737-9 Main Module (D 6978-7 board) Parts List Cont.***Connectors***

J9		C 6871-5	Header, 6 Pin
J10		C 6850-9	Header, 4 Pin
J11		C 7077-8	Retainer, 3 Pin
J100	J200	C 6777-4	Phone Jack
J500	J800	D 6619-7	10" Ribbon Assy
J600	J700	D 6620-5	6" Ribbon Assy

Misc.

Mounts U1, U2:

(2)	C 1889-2	6-32 Nut
(2)	C 2176-3	6-32 X .5 Screw
(2)	C 5341-0	Heatsink
(2)	C 5594-4	Star Washer

Mounts U104, U204:

(2)	C 3450-1	14 Pin Socket
-----	----------	---------------

Covers For J100, J200:

(2)	C 6778-2	Cover, Phone Jk
-----	----------	-----------------

Circuit Board: D 6978-7

Q42753-6 Main Module (D 7150-2 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C3	C 4303-1	1000μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 6094-9	33μF
C100	C200 C 5053-1	18μF
C101	C201 C 2821-4	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6804-6	.1μF
C105	C205 C 6950-7	82pF
C106	C206 C 6950-7	82pF
C108	C208 C 6812-9	47pF
C112	C212 C 6803-8	.12μF
C113	C213 C 6802-0	.47μF
C114	C214 C 3729-8	100μF
C115	C215 C 3729-8	100μF
C116	C216 C 6802-0	.47μF
C117	C217 C 6803-8	.12μF
C118	C218 C 6812-9	47pF
C122	C222 C 6811-1	100pF
C124	C224 C 6809-5	220pF
C125	C225 C 3729-8	100μF
C127	C227 C 3729-8	100μF
C128	C228 C 5243-8	.1μF
C130	C230 C 6814-5	12pF
C133	C233 C 2821-4	10pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6814-5	12pF
C139	C239 C 6814-5	12pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 5362-6	2.2μF
C145	C245 C 6814-5	12pF
C146	C246 C 6809-5	220pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C 149	C249 C 6808-7	470pF
C152	C252 C 6809-5	220pF
C153	C253 C 6804-6	.1μF

Diodes

D1	C 2851-1	1N4004
D2	C 2851-1	1N4004
D3	C 2851-1	1N4004
D4	C 2851-1	1N4004
D5	C 2851-1	1N4004

D6	C 2851-1	1N4004
D7	C 2851-1	1N4004
D8	C 3181-2	1N4148
D9	C 3549-0	1N961B
D104	D204 C 2851-1	1N4004
D105	D205 C 2851-1	1N4004
D106	D206 C 2851-1	1N4004
D107	D207 C 2851-1	1N4004
D108	D208 C 3181-2	1N4148
D109	D209 C 3181-2	1N4148
D110	D210 C 3181-2	1N4148
D111	D211 C 3181-2	1N4148
D112	D212 C 3181-2	1N4148
D113	D213 C 3181-2	1N4148
D114	D214 C 3181-2	1N4148
D115	D215 C 3181-2	1N4148
D120	D220 C 3181-2	1N4148
D121	D221 C 3181-2	1N4148
D122	D222 C 3181-2	1N4148
D123	D223 C 5061-4	1N3070
D124	D224 C 5061-4	1N3070

Resistor Networks

N100	N200	D 4669-4	Balanced Input
N101	N201	D 6081-0	Resistor Network-B
N102	N202	D 6082-8	Resistor Network-C

Transistors

Q1	C 7458-0	2N4123
Q2	C 3625-8	2N4125
Q100	Q200 D 2961-7	SEL 2N3859A
Q101	Q201 C 3578-9	MPSA93
Q102	Q202 C 3810-6	MPSA43/A42
Q103	Q203 C 3786-8	PN4250A
Q104	Q204 C 3625-8	2N4125
Q105	Q205 C 3578-9	MPSA93
Q106	Q206 C 3625-8	2N4125
Q107	Q207 C 3786-8	PN4250A
Q108	Q208 D 2961-7	SEL 2N3859A
Q109	Q209 D 2961-7	SEL 2N3859A
Q110	Q210 C 3810-6	MPSA43/A42
Q111	Q211 D 2961-7	SEL 2N3859A
Q112	Q212 C 3625-8	2N4125
Q113	Q213 C 3625-8	2N4125
Q115	Q215 D 2962-5	MPS8097/MPSA18
Q116	Q216 C 3786-8	PN4250A
Q117	Q217 D 2961-7	SEL 2N3859A
Q118	Q218 D 2961-7	SEL 2N3859A
Q119	Q219 C 3625-8	2N4125
Q120	Q220 C 3625-8	2N4125
Q121	Q221 C 7458-0	2N4123
Q122	Q222 C 7458-0	2N4123

Q42753-6 Main Module (D 7150-2 board) Parts List Cont.

Resistors

R1	A10265-53621	53.6K
R2	A10266-2402	24 OHM
R3	A10266-2402	24 OHM
R4	A10265-46421	46.4K
R11	A10266-5621	5.6K
R12	A10266-4331	43K
R13	A10266-1021	1K
R14	A10266-8221	8.2K
R15	A10266-6211	620 Ohm
R100	R200	C 7592-6 Header
R101	R201	A10265-49911 4.99K
R102	R202	A10266-1021 1K
R103	R203	A10266-1041 100K
R104	R204	A10266-2721 2.7K
R105	R205	A10266-2721 2.7K
R106	R206	A10266-1231 12K
R107	R207	A10266-4731 47K
R108	R208	A10266-8211 820 Ohm
R109	R209	A10266-6801 68 Ohm
R110	R210	A10266-4731 47K
R111	R211	A10266-1231 12K
R112	R212	A10266-5131 51K
R113	R213	A10266-4721 4.7K
R114	R214	A10266-4721 4.7K
R115	R215	A10266-5141 510K
R116	R216	A10266-3351 3.3M
R117	R217	A10266-4731 47K
R118	R218	A10266-2711 270 Ohm
R119	R219	A10266-3911 390 Ohm
R120	R220	A10266-2711 270 Ohm
R121	R221	C 5062-2 100K Pot
R122	R222	A10266-2741 270K
R123	R223	A10266-2731 27K
R124	R224	A10266-6821 6.8K
R125	R225	C 7782-3 100 Ohm
R126	R226	C 7782-3 100 Ohm
R127	R227	A10266-6821 6.8K
R128	R228	A10266-1031 10K
R129	R229	A10266-1041 100K
R130	R230	A10266-1041 100K
R131	R231	A10266-1031 10K
R132	R232	C 5062-2 100K Pot
R133	R233	A10266-2741 270K
R134	R234	A10266-2731 27K
R135	R235	C 7782-3 100 Ohm
R136	R236	A10266-6821 6.8K
R137	R237	C 7782-3 100 Ohm
R138	R238	A10266-6821 6.8K
R139	R239	A10266-8211 820 Ohm
R140	R240	A10266-6801 68 Ohm
R141	R241	A10266-1541 150K

R142	R242	A10266-1541	150K
R146	R246	A10266-1031	10K
R147	R247	C 7781-5	200 Ohm
R148	R248	A10266-2721	2.7K
R149	R249	C 7781-5	200 Ohm
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1031	10K
R152	R252	A10266-1231	12K
R154	R254	C 7782-3	100 Ohm
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10266-9121	9.1K
R159	R259	A10266-1031	10K
R161	R261	A10266-4701	47 Ohm
R162	R262	A10266-4701	47 Ohm
R165	R265	A10265-53611	5.36K
R167	R267	A10266-1021	1K
R168	R268	A10265-95301	953 Ohm
R170	R270	A10266-1021	1K
R171	R271	A10265-95301	953 Ohm
R174	R274	A10265-38311	3.83K
R175	R275	A10265-11811	1.18K
R176	R276	A10266-1041	100K
R177	R277	C 5062-2	100K Pot
R178	R278	A10266-1231	12K
R179	R279	A10266-4731	47K
R180	R280	A10266-4711	470 Ohm
R181	R281	A10266-4721	4.7K
R182	R282	A10266-2201	22 Ohm
R183	R283	A10266-2421	2.4K
R185	R285	A10266-2421	2.4K
R186	R286	A10266-1051	1M

Switches

S2	C 7325-1	DPDT, Gnd Lift
S3	C 7363-2	DPDT, Sensitivity
S100	C 6781-6	6P3T, St/Mono

IC's

U1	C 5095-2	MC7815
U2	C 5096-0	MC7915
U100	U200	C 6500-0 UPA77 PNP
U103	U203	C 6910-1 UPA76 NPN
U104	U204	C 6900-2 MC34084P

Q42753-6 Main Module (D 7150-2 board) Parts List Cont.

Connectors

J9		C 6871-5	Header, 6 Pin
J10		C 6850-9	Header, 4 Pin
J11		C 7077-8	Retainer, 3 Pin
J100	J200	C 6777-4	Phone Jack
J500	J800	D 6619-7	10" Ribbon Assy
J600	J700	D 6620-5	6" Ribbon Assy

Misc.

Mounts U1, U2:

(2)	C 1889-2	6-32 Nut
(2)	C 2176-3	6-32 X .5 Screw
(2)	C 5341-0	Heatsink
(2)	C 5594-4	Star Washer

Mounts U104, U204:

(2)	C 3450-1	14 Pin Socket
-----	----------	---------------

Covers For J100, J200:

(2)	C 6778-2	Cover, Phone Jk
-----	----------	-----------------

Circuit Board: D 7150-2

Q42777-5 Main Module (D 7251-8 board) Parts List

Capacitors

C1	C 3913-8	470μF
C2	C 3913-8	470μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 6094-9	33μF
C8	C 6806-1	.01μF
C100 C200	C 5311-3	22μF
C101 C201	C 2820-6	5pF
C103 C203	C 6805-3	.022μF
C104 C204	C 6804-6	.1μF
C105 C205	C 6812-9	47pF
C106 C206	C 6812-9	47pF
C108 C208	C 6814-5	12pF
C112 C212	C 6803-8	.12μF
C113 C213	C 6802-0	.47μF
C114 C214	C 8026-4	100μF
C115 C215	C 8026-4	100μF
C116 C216	C 6802-0	.47μF
C117 C217	C 6803-8	.12μF
C118 C218	C 6814-5	12pF
C122 C222	C 6811-1	100pF
C123 C223	C 6812-9	47pF
C124 C224	C 6812-9	47pF
C125 C225	C 8026-4	100μF
C127 C227	C 8026-4	100μF
C128 C228	C 5243-8	.1μF
C130 C230	C 6814-5	12pF
C133 C233	C 6814-5	12pF
C134 C234	C 6805-3	.022μF
C135 C235	C 6805-3	.022μF
C136 C236	C 6808-7	470pF
C137 C237	C 6808-7	470pF
C138 C238	C 6814-5	12pF
C139 C239	C 6814-5	12pF
C140 C240	C 6812-9	47pF
C141 C241	C 6812-9	47pF
C144 C244	C 8026-4	100μF
C145 C245	C 6814-5	12pF
C146 C246	C 6809-5	220pF
C147 C247	C 6806-1	.01μF
C148 C248	C 6810-3	180pF
C 149 C249	C 6808-7	470pF
C152 C252	C 6809-5	220pF
C153 C253	C 6804-6	.1μF

Diodes

D1	C 2851-1	1N4004
D2	C 2851-1	1N4004
D3	C 2851-1	1N4004
D4	C 2851-1	1N4004
D5	C 2851-1	1N4004

D6	C 2851-1	1N4004
D7	C 2851-1	1N4004
D8	C 3181-2	1N4148
D9	C 3549-0	1N916B 10V
D104 D204	C 2851-1	1N4004
D105 D205	C 2851-1	1N4004
D106 D206	C 2851-1	1N4004
D107 D207	C 2851-1	1N4004
D108 D208	C 3181-2	1N4148
D109 D209	C 3181-2	1N4148
D110 D210	C 3181-2	1N4148
D111 D211	C 5061-4	1N3070
D112 D212	C 3181-2	1N4148
D113 D213	C 3181-2	1N4148
D114 D214	C 3181-2	1N4148
D115 D215	C 3181-2	1N4148
D120 D220	C 3181-2	1N4148
D121 D221	C 3181-2	1N4148
D122 D222	C 3181-2	1N4148
D123 D223	C 5061-4	1N3070
D124 D224	C 5061-4	1N3070

Resistor Networks

N100 N200	D 4669-4	Balanced Input Trim
N101 N201	D 6081-0	Resistor Network-B
N102 N202	D 6082-8	Resistor Network-C

Transistors

Q1	C 7458-0	2N4123
Q2	C 3625-8	2N4125
Q100 Q200	D 2961-7	SEL 2N3859A
Q101 Q201	C 3578-9	MPSA93
Q102 Q202	C 3810-6	MPSA43/A42
Q103 Q203	C 3786-8	PN4250A
Q104 Q204	C 3625-8	2N4125
Q105 Q205	C 3578-9	MPSA93
Q106 Q206	C 3625-8	2N4125
Q107 Q207	C 3786-8	PN4250A
Q108 Q208	D 2961-7	SEL 2N3859A
Q109 Q209	D 2961-7	SEL 2N3859A
Q110 Q210	C 3810-6	MPSA43/A42
Q111 Q211	D 2961-7	SEL 2N3859A
Q112 Q212	C 3625-8	2N4125
Q113 Q213	C 3625-8	2N4125
Q115 Q215	D 2962-5	MPS8097
Q116 Q216	C 3786-8	PN4250A
Q117 Q217	D 2961-7	SEL 2N3859A
Q118 Q218	D 2961-7	SEL 2N3859A
Q119 Q219	C 3625-8	2N4125
Q120 Q220	C 3625-8	2N4125
Q121 Q221	C 7458-0	2N4123
Q122 Q222	C 7458-0	2N4123

Q42777-5 Main Module (D 7251-8 board) Parts List Cont.

Resistors

Resistors			
R1	A10265-53621	53.6K	
R2	A10266-2402	24 Ohm	
R3	A10266-2402	24 Ohm	
R4	A10265-46421	46.4K	
R11	A10266-5621	5.6K	
R12	A10266-4331	43K	
R13	A10266-1021	1K	
R14	A10266-8221	8.2K	
R15	A10266-6211	620 Ohm	
R100	R200	C 7592-6	Header
R101	R201	A10265-49911	4.99K
R102	R202	A10266-1021	1K
R103	R203	A10266-1041	100K
R104	R204	A10266-2721	2.7K
R105	R205	A10266-2721	2.7K
R106	R206	A10266-1231	12K
R107	R207	A10266-6831	68K
R108	R208	A10266-8211	820 Ohm
R109	R209	A10266-6801	68 Ohm
R110	R210	A10266-6831	68K
R111	R211	A10266-1231	12K
R112	R212	A10266-5131	51K
R113	R213	A10266-4721	4.7K
R114	R214	A10266-4721	4.7K
R115	R215	A10266-5141	510K
R116	R216	A10266-3351	3.3M
R117	R217	A10266-4731	47K
R118	R218	A10266-2711	270 Ohm
R119	R219	A10266-3911	390 Ohm
R120	R220	A10266-2711	270 Ohm
R121	R221	C 5062-2	100K Pot
R122	R222	A10266-2741	270K
R123	R223	A10266-2731	27K
R124	R224	A10266-6821	6.8K
R125	R225	C 7782-3	100 Ohm
R126	R226	C 7782-3	100 Ohm
R127	R227	A10266-6821	6.8K
R128	R228	A10266-1031	10K
R129	R229	A10266-1041	100K
R130	R230	A10266-1041	100K
R131	R231	A10266-1031	10K
R132	R232	C 5062-2	100K Pot
R133	R233	A10266-2741	270K
R134	R234	A10266-2731	27K
R135	R235	C 7782-3	100 Ohm
R136	R236	A10266-6821	6.8K
R137	R237	C 7782-3	100 Ohm
R138	R238	A10266-6821	6.8K
R139	R239	A10266-8211	820 Ohm
R140	R240	A10266-6801	68 Ohm
R141	R241	A10266-1541	150K
R142	R242	A10266-1541	150K
R146	R246	A10266-1031	10K
R147	R247	C 7781-5	200 Ohm
R148	R248	A10266-2721	2.7K
R149	R249	C 7781-5	200 Ohm
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1031	10K
R152	R252	A10266-1231	12K
R153	R253	C 5868-2	Zero Ohm
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10266-9121	9.1K
R159	R259	A10266-1031	10K
R161	R261	A10266-4701	47 Ohm
R162	R262	A10266-4701	47 Ohm
R167	R267	A10266-1021	1K
R168	R268	A10265-95301	953 Ohm
R170	R270	A10266-1021	1K
R171	R271	A10265-95301	953 Ohm
R174	R274	A10265-24921	24.9K
R175	R275	A10265-78711	7.87K
R176	R276	A10265-24921	24.9K
R179	R279	A10266-4731	47K
R180	R280	A10266-4711	470 Ohm
R181	R281	A10266-4721	4.7K
R182	R282	A10266-2201	22 Ohm
R183	R283	A10266-2421	2.4K
R185	R285	A10266-2421	2.4K
R186	R286	A10266-1051	1M
Switches			
S2		C 7325-1	DPDT Gnd Lift
S3		C 7363-2	DPDT Sensitivity
S100		C 6781-6	6P3T Stereo/Mono
IC's			
U1		C 5095-2	MC7815
U2		C 5096-0	MC7915
U100	U200	C 6911-9	UPA75 PNP
U103	U203	C 6910-1	UPA76 NPN
U104	U204	C 6900-2	MC34084P

Q42777-5 Main Module (D 7251-8 board) Parts List Cont.***Connectors***

J1	C 7593-4	Header, 5 Pin
J9	C 7527-2	Header, 6 Pin
J10	C 7592-6	Header, 4 Pin
J11	C 7526-4	Header, 3 Pin
J100 J200	C 6777-4	Phone Jack
J500 J800	D 6619-7	10" Ribbon Assy
J600 J700	D 6620-5	6" Ribbon Assy

Misc.

Mounts U1, U2:

(2)	C 1889-2	6-32 Nut
(2)	C 2176-3	6-32 X .5 Screw
(2)	C 5341-0	Heatsink
(2)	C 5594-4	Star Washer

Mounts U104, U204:

(2)	C 3450-1	14 Pin Socket
-----	----------	---------------

Covers For J100, J200:

(2)	C 6778-2	Cover, Phone Jack
-----	----------	-------------------

Strain Relief:

(4)	C 1811-6	Cable Tie
-----	----------	-----------

Circuit Board:

D 7251-8

Q42982-1 Main Module (D 7911-7 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 6804-6	.1μF
C100	C200 C 5311-3	22μF
C101	C201 C 2821-4	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6805-3	.022μF
C105	C205 C 6812-9	47pF
C106	C206 C 6812-9	47pF
C107	C207 C 6804-6	.1μF
C108	C208 C 6814-5	12pF
C109	C209 C 7417-6	.0033μF
C110	C210 C 5362-6	2.2μF
C111	C211 C 6804-6	.1μF
C112	C212 C 6803-8	.12μF
C113	C213 C 6802-0	.47μF
C114	C214 C 8854-9	100μF
C115	C215 C 8854-9	100μF
C116	C216 C 6802-0	.47μF
C117	C217 C 6803-8	.12μF
C118	C218 C 6814-5	12pF
C119	C219 C 6802-0	.47μF
C120	C220 C 6804-6	.1μF
C122	C222 C 6811-1	100pF
C123	C223 C 6812-9	47pF
C124	C224 C 6812-9	47pF
C129	C229 C 6814-5	12pF
C130	C230 C 6813-7	27pF
C133	C233 C 6813-7	27pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6813-7	27pF
C139	C239 C 6813-7	27pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 8576-8	100μF
C145	C245 C 6812-9	47pF
C146	C246 C 6812-9	47pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C 149	C249 C 6808-7	470pF
C150	C250 C 6806-1	.01μF
C151	C251 C 6806-1	.01μF
C152	C252 C 6950-7	82pF
C153	C253 C 6804-6	.1μF
C154	C254 C 8426-6	.1μF

C155	C255	C 6804-6	.1μF
C156	C256	C 6804-6	.1μF
C157	C257	C 6806-1	.01μF

Diodes

D1		C 2851-1	1N4004
D2		C 2851-1	1N4004
D3		C 2851-1	1N4004
D4		C 2851-1	1N4004
D5		C 2851-1	1N4004
D6		C 2851-1	1N4004
D7		C 2851-1	1N4004
D108	D208	C 3181-2	1N4148
D109	D209	C 3181-2	1N4148
D110	D210	C 3181-2	1N4148
D111	D211	C 5061-4	1N3070
D112	D212	C 3181-2	1N4148
D113	D213	C 3181-2	1N4148
D120	D220	C 3181-2	1N4148
D121	D221	C 3181-2	1N4148
D122	D222	C 3181-2	1N4148
D123	D223	C 5061-4	1N3070
D124	D224	C 3181-2	1N4148
D125	D225	C 3181-2	1N4148
D126	D226	C 5061-4	1N3070
D127	D227	C 5061-4	1N3070
D128	D228	C 5061-4	1N3070
D129	D229	C 3181-2	1N4148
D130	D230	C 3181-2	1N4148
D131	D231	C 3181-2	1N4148
D132	D232	C 3181-2	1N4148

Resistor Networks

N100	N200	D 4669-4	Balanced Input Trim
N101	N201	D 6081-0	Resistor Network-B
N102	N202	D 6082-8	Resistor Network-C

Transistors

Q100	Q200	D 2961-7	SEL 2N3859A
Q101	Q201	C 3578-9	MPSA93
Q102	Q202	C 3810-6	MPSA43/A42
Q103	Q203	C 3786-8	PN4250A
Q105	Q205	C 3578-9	MPSA93
Q106	Q206	C 3625-8	2N4125
Q107	Q207	C 3786-8	PN4250A
Q108	Q208	D 2961-7	SEL 2N3859A
Q109	Q209	D 2961-7	SEL 2N3859A
Q110	Q210	C 3810-6	MPSA43/A42
Q112	Q212	C 3625-8	2N4125
Q113	Q213	C 3625-8	2N4125
Q115	Q215	D 2962-5	MPS8097/MPSA18
Q116	Q216	C 3786-8	PN4250A

Q42982-1 Main Module (D 7911-7 board) Parts List Cont.

Q117	Q217	D 2961-7	SEL 2N3859A
Q118	Q218	D 2961-7	SEL 2N3859A
Q119	Q219	C 3625-8	2N4125
Q120	Q220	C 3625-8	2N4125
Q121	Q221	C 7458-0	2N4123
Q122	Q222	C 7458-0	2N4123
Q123	Q223	C 7458-0	2N4123
Q124	Q224	C 3625-8	2N4125

Resistors

R1		A10265-53621	53.6K
R2		A10266-2402	24 Ohm
R3		A10266-2402	24 Ohm
R4		A10265-46421	46.4K
R7		A10266-1041	100K
R8		A10266-2031	20K
R9		A10266-5121	5.1K
R16		A10266-5121	5.1K
R17		A10266-2031	20K
R18		A10266-1041	100K
R100	R200	C 7592-6	Header
R101	R201	A10265-49911	4.99K
R102	R202	A10266-5111	510 Ohm
R103	R203	A10266-1041	100K
R104	R204	A10266-2721	2.7K
R105	R205	A10266-2721	2.7K
R106	R206	A10266-1231	12K
R107	R207	A10266-6831	68K
R108	R208	A10266-8211	820 Ohm
R109	R209	A10266-6801	68 Ohm
R110	R210	A10266-6831	68K
R111	R211	A10266-1231	12K
R112	R212	A10266-5131	51K
R113	R213	A10266-4721	4.7K
R114	R214	A10266-4721	4.7K
R115	R215	A10266-5141	510K
R116	R216	A10266-2751	2.7M
R117	R217	A10266-4731	47K
R118	R218	A10266-2711	270 Ohm
R119	R219	A10266-3911	390 Ohm
R120	R220	A10266-2711	270 Ohm
R121	R221	C 5062-2	100K Pot
R122	R222	A10266-2741	270K
R123	R223	A10266-2732	27K
R124	R224	A10266-6821	6.8K
R125	R225	C 7782-3	100 Ohm
R126	R226	C 7782-3	100 Ohm
R127	R227	A10266-6821	6.8K
R128	R228	A10266-1031	10K
R129	R229	A10266-1041	100K
R130	R230	A10266-1041	100K
R131	R231	A10266-1031	10K

R132	R232	C 5062-2	100K Pot
R133	R233	A10266-2741	270K
R134	R234	A10266-2732	27K
R135	R235	C 7782-3	100 Ohm
R136	R236	A10266-6821	6.8K
R137	R237	C 7782-3	100 Ohm
R138	R238	A10266-6821	6.8K
R139	R239	A10266-8211	820 Ohm
R140	R240	A10266-6801	68 Ohm
R141	R241	A10266-1541	150K
R142	R242	A10266-1541	150K
R143	R243	A10266-1041	100K
R144	R244	A10266-1041	100K
R145	R245	A10266-1851	1.8M
R146	R246	A10266-1031	10K
R147	R247	C 7781-5	200 Ohm
R148	R248	A10266-2721	2.7K
R149	R249	C 7781-5	200 Ohm
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1031	10K
R152	R252	A10266-1231	12K
R153	R253	C 5868-2	Zero Ohm
R154	R254	A10265-12131	121K
R155	R255	A10266-1321	1.3K
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10266-9121	9.1K
R159	R259	A10266-1021	1K
R160	R260	A10265-10021	10K
R161	R261	A10266-4701	47 Ohm
R162	R262	A10266-4701	47 Ohm
R163	R263	A10265-12131	121K
R164	R264	A10265-10021	10K
R165	R265	A10265-12131	121K
R166	R266	A10266-1851	1.8M
R167	R267	A10265-10011	1K
R168	R268	A10265-95301	953 Ohm
R170	R270	A10265-10011	1K
R171	R271	A10265-95301	953 Ohm
R173	R273	A10265-10011	10K
R174	R274	A10265-24921	24.9K
R175	R275	A10265-78711	7.87K
R176	R276	A10265-24921	24.9K
R177	R277	A10265-22111	22.1K
R179	R279	A10266-1321	1.3K
R180	R280	A10266-4711	470 Ohm
R181	R281	A10266-4721	4.7K
R182	R282	A10266-2201	22 Ohm
R183	R283	A10266-2421	2.4K
R184	R284	A10266-4741	470K
R185	R285	A10266-2421	2.4K
R186	R286	A10266-2751	2.7M

Q42982-1 Main Module (D 7911-7 board) Parts List Cont.

R187	R287	A10266-3631	36K
R188	R288	A10266-3631	36K
R189	R289	A10266-2731	27K
R190	R290	A10266-2051	2M
R191	R291	A10266-3331	33K
R192	R292	A10266-1031	10K
R193	R293	A10266-1031	10K
R194	R294	A10266-1041	100K
R195	R295	A10266-3021	3K
R196	R296	A10266-4721	4.7K
R197	R297	A10266-1031	10K
R198	R298	A10266-4721	4.7K
R199	R299	A10266-1031	10K
R909	R1009	A10266-4741	470K
R910	R1010	A10266-4741	470K
R911	R1011	A10266-1521	1.5K
R912	R1012	A10266-4711	470 Ohm
R913	R1013	A10266-1051	1M
R914	R1014	A10266-1051	1M
R915	R1015	A10266-2201	22 Ohm
R916	R1016	A10266-2201	22 Ohm

Switches

S2	C 7325-1	DPDT Gnd Lift
S3	C 7960-5	DP3T Sensitivity
S100	C 6781-6	6P3T Stereo/Mono

IC's

U1	C 5095-2	MC7815
U2	C 5096-0	MC7915
U100	U200	C 6911-9
U101	U201	C 4345-2
U102	U202	C 4345-2
U103	U203	C 6910-1
U104	U204	C 7558-7

Connectors

J1	C 7593-4	Header, 5 Pin
J2	C 4508-5	IC Socket, 16 Pin
J11	C 7526-4	Header, 3 Pin
J100	J200	C 6777-4
J101	J201	C 7592-6
J500	J800	D 6619-7
J600	J700	D 6620-5

Misc.

Mounts U1, U2:		
(2)	C 1889-2	6-32 Nut
(2)	C 2176-3	6-32 X .5 Screw
(2)	C 5341-0	Heatsink
(2)	C 5594-4	Star Washer
Mounts U104, U204:		
(2)	C 3450-1	14 Pin Socket
Covers For J100, J200:		
(2)	C 6778-2	Cover, Phone Jack
Strain Relief:		
(4)	C 1811-6	Cable Tie
Circuit Board: D 7911-7		

Q43037-3 Main Module (D 7993-5 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 8897-8	.1μF
C100	C200 C 5311-3	22μF
C101	C201 C 2821-4	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6805-3	.022μF
C105	C205 C 6812-9	47pF
C106	C206 C 6812-9	47pF
C107	C207 C 8897-8	.1μF
C108	C208 C 6814-5	12pF
C109	C209 C 7417-6	.0033μF
C110	C210 C 5362-6	2.2μF
C111	C211 C 8897-8	.1μF
C112	C212 C 8991-9	.47μF
C113	C213 C 8986-9	15μF
C114	C214 C 8854-9	100μF
C115	C215 C 8854-9	100μF
C116	C216 C 8986-9	15μF
C117	C217 C 8991-9	.47μF
C118	C218 C 6814-5	12pF
C119	C219 C 6802-0	.47μF
C120	C220 C 8897-8	.1μF
C122	C222 C 6811-1	100pF
C123	C223 C 6812-9	47pF
C124	C224 C 6812-9	47pF
C129	C229 C 6814-5	12pF
C130	C230 C 6813-7	27pF
C133	C233 C 6813-7	27pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6813-7	27pF
C139	C239 C 6813-7	27pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 8576-8	100μF
C145	C245 C 6812-9	47pF
C146	C246 C 6812-9	47pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C149	C249 C 6808-7	470pF
C150	C250 C 6806-1	.01μF
C151	C251 C 6806-1	.01μF
C152	C252 C 6950-7	82pF 5%
C153	C253 C 8897-8	.1μF
C154	C254 C 8426-6	.1μF 250V

C155	C255	C 8897-8	.1μF
C156	C256	C 8897-8	.1μF
C157	C257	C 6806-1	.01μF

Diodes

D1		C 2851-1	1N4004
D2		C 2851-1	1N4004
D3		C 2851-1	1N4004
D4		C 2851-1	1N4004
D5		C 2851-1	1N4004
D6		C 2851-1	1N4004
D7		C 2851-1	1N4004
D108	D208	C 3181-2	1N4148
D109	D209	C 3181-2	1N4148
D110	D210	C 3181-2	1N4148
D111	D211	C 5061-4	1N3070
D112	D212	C 3181-2	1N4148
D113	D213	C 3181-2	1N4148
D114	D214	C 3181-2	1N4148
D115	D215	C 3181-2	1N4148
D120	D220	C 3181-2	1N4148
D121	D221	C 3181-2	1N4148
D122	D222	C 3181-2	1N4148
D123	D223	C 5061-4	1N3070
D124	D224	C 3181-2	1N4148
D125	D225	C 3181-2	1N4148
D126	D226	C 5061-4	1N3070
D127	D227	C 5061-4	1N3070
D128	D228	C 5061-4	1N3070
D129	D229	C 3181-2	1N4148
D130	D230	C 3181-2	1N4148
D131	D231	C 3181-2	1N4148
D132	D232	C 3181-2	1N4148

Transistors

Q100	Q200	D 2961-7	NPN 2N3859A
Q101	Q201	C 3578-9	PNP MPSA93
Q102	Q202	C 3810-6	NPN MPSA43
Q103	Q203	C 3786-8	PNP PN4250
Q105	Q205	C 3578-9	PNP MPSA93
Q106	Q206	C 3625-8	NPN 2N4125
Q107	Q207	C 3786-8	PNP PN4250
Q108	Q208	D 2961-7	NPN 2N3859A
Q109	Q209	D 2961-7	NPN 2N3859A
Q110	Q210	C 3810-6	NPN MPSA43
Q112	Q212	C 3625-8	NPN 2N4125
Q113	Q213	C 3625-8	NPN 2N4125
Q115	Q215	D 2962-5	NPN MPS8097
Q116	Q216	C 3786-8	PNP PN4250
Q117	Q217	D 2961-7	NPN 2N3859A
Q118	Q218	D 2961-7	NPN 2N3859A
Q119	Q219	C 3625-8	NPN 2N4125

Q43037-3 Main Module (D 7993-5 board) Parts List Cont.

Q120	Q220	C 3625-8	NPN 2N4125
Q121	Q221	C 7458-0	NPN 2N4123
Q122	Q222	C 7458-0	NPN 2N4123
Q123	Q223	C 7458-0	NPN 2N4123
Q124	Q224	C 3625-8	NPN 2N4125
Q125	Q225	C 3786-8	PNP PN4250A
Q126	Q226	C 5891-4	NPN MTS105

Resistors (.25W 5% unless noted otherwise)

N101	N201	D 7944-8	Resistor Network
N102	N202	D 6082-8	Resistor Network
R1		A10265-53621	53.6K 1%
R2		C 7340-0	24 5W
R3		C 7340-0	24 5W
R4		A10265-46421	46.4K 1%
R7		A10266-1041	100K
R8		A10266-2031	20K
R9		A10266-5121	5.1K
R10		OPEN	
R16		A10266-5121	5.1K
R17		A10266-2031	20K
R18		A10266-1041	100K
R100	R200	C 7592-6	4 Pin Header
R101	R201	A10265-49911	4.99K 1%
R102	R202	A10266-5111	510
R103	R203	A10265-10031	100K 1%
R104	R204	A10266-2721	2.7K
R105	R205	A10266-2721	2.7K
R106	R206	A10266-1231	12K
R107	R207	A10266-6831	68K
R108	R208	A10266-8211	820
R109	R209	A10266-6801	68
R110	R210	A10266-6831	68K
R111	R211	A10266-1231	12K
R112	R212	A10266-5131	51K
R113	R213	A10266-4721	4.7K
R114	R214	A10266-4721	4.7K
R115	R215	A10266-5141	510K
R116	R216	A10266-2751	2.7M
R117	R217	A10266-4731	47K
R118	R218	A10266-2711	270
R119	R219	A10266-3911	390
R120	R220	A10266-2711	270
R121	R221	C 5062-2	100K Pot (-ODEP)
R122	R222	A10266-2741	270K
R123	R223	A10266-2732	27K .5W
R124	R224	A10266-6821	6.8K
R125	R225	C 7782-3	100 Flame Proof
R126	R226	C 7782-3	100 Flame Proof
R127	R227	A10266-6821	6.8K
R128	R228	A10266-1031	10K
R129	R229	A10266-1041	100K

R130	R230	A10266-1041	100K
R131	R231	A10266-1031	10K
R132	R232	C 5062-2	100K Pot (+ODEP)
R133	R233	A10266-2741	270K
R134	R234	A10266-2732	27K .5W
R135	R235	C 7782-3	100 Flame Proof
R136	R236	A10266-6821	6.8K
R137	R237	C 7782-3	100 Flame Proof
R138	R238	A10266-6821	6.8K
R139	R239	A10266-8211	820
R140	R240	A10266-6801	68
R141	R241	A10266-1541	150K
R142	R242	A10266-1541	150K
R143	R243	A10266-1041	100K
R144	R244	A10266-1041	100K
R145	R245	A10266-1851	1.8M
R146	R246	A10266-1031	10K
R147	R247	C 7781-5	200 .5W Flame Proof
R148	R248	A10266-2721	2.7K
R149	R249	C 7781-5	200 .5W Flame Proof
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1031	10K
R152	R252	A10265-11821	11.8K 1%
R153	R253	A10124-24	JUMPER
R154	R254	C 8261-7	121K 0.1%
R155	R255	A10266-1321	1.3K
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10265-11821	11.8K 1%
R159	R259	A10266-1021	1K
R160	R260	C 8260-9	10K 0.1%
R161	R261	A10266-4701	47
R162	R262	A10266-4701	47
R163	R263	C 8261-7	121K 0.1%
R164	R264	C 8260-9	10K 0.1%
R165	R265	C 8261-7	121K 0.1%
R166	R266	A10266-1851	1.8M
R167	R267	A10265-10011	1K 1%
R168	R268	A10265-96701	967 1%
R170	R270	A10265-10011	1K 1%
R171	R271	A10265-95301	953 1%
R173	R273	C 8260-9	10K 0.1%
R174	R274	A10265-24921	24.9K 1%
R175	R265	A10265-78711	7.87K 1%
R176	R276	A10265-24921	24.9K 1%
R177	R277	A10265-22121	22.1K 1%
R179	R279	A10266-1321	1.3K
R180	R280	A10266-4711	470
R181	R281	A10266-4721	4.7K
R182	R282	A10266-2201	22
R183	R283	A10266-2421	2.4K
R184	R284	A10266-4741	470K

Q43037-3 Main Module (D 7993-5 board) Parts List Cont.

R185	R285	A10266-2421	2.4K
R186	R286	A10266-2751	2.7M
R187	R287	A10266-3631	36K
R188	R288	A10266-3631	36K
R189	R289	A10266-2731	27K
R190	R290	A10266-2051	2M
R191	R291	A10266-3331	33K
R192	R292	A10266-1031	10K
R193	R293	A10266-1031	10K
R194	R294	A10266-1041	100K
R195	R295	A10266-3021	3K
R196	R296	A10266-4721	4.7K
R197	R297	A10266-1031	10K
R198	R298	A10266-4721	4.7K
R199	R299	A10266-1031	10K
R906	R1006	OPEN	
R907	R1007	OPEN	
R908	R1008	OPEN	
R909	R1009	A10266-4741	470K
R910	R1010	A10266-4741	470K
R911	R1011	A10266-1521	1.5K
R912	R1012	A10266-4711	470
R913	R1013	A10266-1051	1M
R914	R1014	A10266-1051	1M
R915	R1015	A10266-2201	22
R916	R1016	A10266-2201	22
R917	R1017	A10265-10021	10K 1%
R918	R1018	A10265-10021	10K 1%
R919	R1019	A10265-10021	10K 1%
R920	R1020	A10265-10021	10K 1%
R921	R1021	C 9079-2	200 Pot (CMR Null)

Switches

S2	C 7325-1	Ground Lift
S3	C 7960-5	Sensitivity
S4	C 6781-6	Stereo/Mono

IC's

U1	C 5095-2	UA7815
U2	C 5096-0	UA7915
U100	U200	C 6911-9
U101	U201	C 4345-2
U102	U202	C 4345-2
U103	U203	C 6910-1
U104	U204	C 7558-7

Misc.

Board	D 7993-5	
Socket	C 3450-1	14 Pin (Qty 6)
Nut	A10102-5	Hex 6-32 (Qty 2)
Heatsink	C 5341-0	TO-220 (Qty 2)
Torq Spreader	C 6541-4	(Qty 2)
Washer	A10096-5	#6, Split (Qty 2)
Screw	A10240-0608	Stainless (Qty 2)
J1	C 7593-4	5 Pin Header
J2	C 4508-5	16 Pin Socket
J11	C 7526-4	3 Pin Header
J100	J200	C 6777-4
Cover	C 6778-2	Phone Jack (Qty 2)
J500	J800	D 6619-7
J600	J700	D 6620-5
Cable Tie	C 1811-6	6 Inch Ribbon (Qty 4)

Q43132-2 Main Module (D 8283-0 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 8897-8	.1μF
C100	C200 C 5311-3	22μF
C101	C201 C 9464-6	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6805-3	.022μF
C105	C205 C 6812-9	47pF
C106	C206 C 6812-9	47pF
C107	C207 C 8897-8	.1μF
C108	C208 C 6814-5	12pF
C109	C209 C 7417-6	.0033μF
C110	C210 C 5362-6	2.2μF
C111	C211 C 8897-8	.1μF
C112	C212 C 8991-9	.47μF
C113	C213 C 8986-9	15μF
C114	C214 C 8854-9	100μF
C115	C215 C 8854-9	100μF
C116	C216 C 8986-9	15μF
C117	C217 C 8991-9	.47μF
C118	C218 C 6814-5	12pF
C119	C219 C 6802-0	.47μF
C120	C220 C 8897-8	.1μF
C122	C222 C 6811-1	100pF
C123	C223 C 6812-9	47pF
C124	C224 C 6812-9	47pF
C129	C229 C 6814-5	12pF
C130	C230 C 6813-7	27pF
C133	C233 C 6813-7	27pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6813-7	27pF
C139	C239 C 6813-7	27pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 8576-8	100μF
C145	C245 C 6812-9	47pF
C146	C246 C 6812-9	47pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C149	C249 C 6808-7	470pF
C150	C250 C 6806-1	.01μF
C151	C251 C 6806-1	.01μF
C152	C252 C 6950-7	82pF 5%
C153	C253 C 8897-8	.1μF
C154	C254 C 8426-6	.1μF 250V

C155	C255	C 8897-8	.1μF
C156	C256	C 8897-8	.1μF
C157	C257	C 6806-1	.01μF
C158	C258	C 6807-9	.001μF
C159	C259	C 6807-9	.001μF
C160	C260	C 6811-1	100pF
C161	C261	C 6811-1	100pF

Diodes

D1		C 2851-1	1N4004
D2		C 2851-1	1N4004
D3		C 2851-1	1N4004
D4		C 2851-1	1N4004
D5		C 2851-1	1N4004
D6		C 2851-1	1N4004
D7		C 2851-1	1N4004
D108	D208	C 3181-2	1N4148
D109	D209	C 3181-2	1N4148
D110	D210	C 3181-2	1N4148
D111	D211	C 5061-4	1N3070
D112	D212	C 3181-2	1N4148
D113	D213	C 3181-2	1N4148
D114	D214	C 3181-2	1N4148
D115	D215	C 3181-2	1N4148
D120	D220	C 3181-2	1N4148
D121	D221	C 3181-2	1N4148
D122	D222	C 3181-2	1N4148
D123	D223	C 5061-4	1N3070
D124	D224	C 3181-2	1N4148
D125	D225	C 3181-2	1N4148
D126	D226	C 5061-4	1N3070
D127	D227	C 5061-4	1N3070
D128	D228	C 5061-4	1N3070
D129	D229	C 3181-2	1N4148
D130	D230	C 3181-2	1N4148
D131	D231	C 3181-2	1N4148
D132	D232	C 3181-2	1N4148
D133	D233	C 3181-2	1N4148
D134	D234	C 3181-2	1N4148

Transistors

Q100	Q200	D 2961-7	NPN 2N3859A
Q101	Q201	C 3578-9	PNP MPSA93
Q102	Q202	C 3810-6	NPN MPSA43
Q103	Q203	C 3786-8	PNP PN4250
Q105	Q205	C 3578-9	PNP MPSA93
Q106	Q206	C 3625-8	NPN 2N4125
Q107	Q207	C 3786-8	PNP PN4250
Q108	Q208	C 5891-4	NPN MTS105
Q109	Q209	D 2961-7	NPN 2N3859A
Q110	Q210	C 3810-6	NPN MPSA43
Q112	Q212	C 3625-8	NPN 2N4125

Q43132-2 Main Module (D 8283-0 board) Parts List Cont.

Q113	Q213	C 3625-8	NPN 2N4125
Q115	Q215	D 2962-5	NPN MPS8097
Q116	Q216	C 3786-8	PNP PN4250
Q117	Q217	D 2961-7	NPN 2N3859A
Q118	Q218	D 2961-7	NPN 2N3859A
Q119	Q219	C 3625-8	NPN 2N4125
Q120	Q220	C 3625-8	NPN 2N4125
Q121	Q221	C 7458-0	NPN 2N4123
Q122	Q222	C 7458-0	NPN 2N4123
Q123	Q223	C 7458-0	NPN 2N4123
Q124	Q224	C 3625-8	NPN 2N4125
Q125	Q225	C 3786-8	PNP PN4250A
Q126	Q226	C 5891-4	NPN MTS105

Resistors

R1		A10265-53621	53.6K 1%
R2		C 7340-0	24 5W
R3		C 7340-0	24 5W
R4		A10265-46421	46.4K 1%
R7		A10266-1041	100K
R8		A10266-2031	20K
R9		A10266-5121	5.1K
R10		OPEN	
R16		A10266-5121	5.1K
R17		A10266-2031	20K
R18		A10266-1041	100K
R100	R200	C 7592-6	4 Pin Header
R101	R201	A10265-49911	4.99K 1%
R102	R202	A10266-5111	510
R103	R203	A10265-10031	100K 1%
R104	R204	A10266-2721	2.7K
R105	R205	A10266-2721	2.7K
R106	R206	A10266-1231	12K
R107	R207	A10266-6831	68K
R108	R208	A10266-8211	820
R109	R209	A10266-5601	56
R110	R210	A10266-6831	68K
R111	R211	A10266-1231	12K
R112	R212	A10266-5131	51K
R113	R213	A10266-4721	4.7K
R114	R214	A10266-4721	4.7K
R115	R215	A10266-5141	510K
R116	R216	A10266-2751	2.7M
R117	R217	A10266-4731	47K
R118	R218	A10265-28701	287 1%
R119	R219	A10265-80601	806 1%
R120	R220	A10265-28701	287 1%
R121	R221	C 5062-2	100K Pot (-ODEP)
R122	R222	A10266-2741	270K
R123	R223	A10266-2732	27K .5W
R124	R224	A10266-6821	6.8K
R125	R225	C 7782-3	100 Flame Proof

R126	R226	C 7782-3	100 Flame Proof
R127	R227	A10266-6821	6.8K
R128	R228	A10266-1331	13K
R129	R229	A10266-1041	100K
R130	R230	A10266-1041	100K
R131	R231	A10266-1331	13K
R132	R232	C 5062-2	100K Pot (+ODEP)
R133	R233	A10266-2741	270K
R134	R234	A10266-2732	27K .5W
R135	R235	C 7782-3	100 Flame Proof
R136	R236	A10266-6821	6.8K
R137	R237	C 7782-3	100 Flame Proof
R138	R238	A10266-6821	6.8K
R139	R239	A10266-8211	820
R140	R240	A10266-5601	56
R141	R241	A10266-1541	150K
R142	R242	A10266-1541	150K
R143	R243	A10266-1041	100K
R144	R244	A10266-1041	100K
R145	R245	A10266-2251	2.2M
R146	R246	A10266-1231	12K
R147	R247	C 8836-6	100 .5W Flame Proof
R148	R248	A10266-2721	2.7K
R149	R249	C 8836-6	100 .5W Flame Proof
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1231	12K
R152	R252	A10265-11521	11.5K 1%
R153	R253	JUMPER	JUMPER
R154	R254	C 8261-7	121K 0.1%
R155	R255	A10266-1321	1.3K
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10265-11321	11.3K 1%
R159	R259	A10266-1021	1K
R160	R260	C 8260-9	10K 0.1%
R161	R261	A10266-4701	47
R162	R262	A10266-4701	47
R163	R263	C 8261-7	121K 0.1%
R164	R264	C 8260-9	10K 0.1%
R165	R265	C 8261-7	121K 0.1%
R166	R266	A10266-2251	2.2M
R167	R267	A10265-10011	1K 1%
R168	R268	A10265-10011	1K 1%
R170	R270	A10265-10011	1K 1%
R171	R271	A10265-10011	1K 1%
R173	R273	C 8260-9	10K 0.1%
R174	R274	A10265-24921	24.9K 1%
R175	R265	A10265-78711	7.87K 1%
R176	R276	A10265-24921	24.9K 1%
R177	R277	A10265-22121	22.1K 1%
R179	R279	A10266-1321	1.3K
R180	R280	A10266-4711	470

Q43132-2 Main Module (D 8283-0 board) Parts List Cont.

R181	R281	A10266-4721	4.7K	Switches		
R182	R282	A10266-2201	22		S2	C 7325-1 Switch / Ground
R183	R283	A10266-2421	2.4K		S3	C 7960-5 Sensitivity
R184	R284	A10266-4741	470K		S4	C 6781-6 Switch, Stereo/Mono
R185	R285	A10266-2421	2.4K	IC's		
R186	R286	A10266-2751	2.7M		U1	C 5095-2 UA7815
R187	R287	A10266-3631	36K		U2	C 5096-0 UA7915
R188	R288	A10266-3631	36K		U100 U200	C 6911-9 UPA75
R189	R289	A10266-2731	27K		U101 U201	C 4345-2 LM339
R190	R290	A10266-2051	2M		U102 U202	C 4345-2 LM339
R191	R291	A10266-3331	33K		U103 U203	C 6910-1 UPA76
R192	R292	A10266-1031	10K		U104 U204	C 7558-7 MC33079P
R193	R293	A10266-1031	10K	Misc.		
R194	R294	A10266-1041	100K		Board	D 8283-0
R195	R295	A10266-3021	3K		Socket	C 3450-1 14 Pin (Qty 6)
R196	R296	A10266-4721	4.7K		Nut	A10102-5 Hex 6-32 (Qty 2)
R197	R297	A10266-1031	10K		Heatsink	C 5341-0 TO-220 (Qty 2)
R198	R298	A10266-4721	4.7K		Spreader	C 6541-4 Torque Sprdr (Qty 2)
R199	R299	A10266-1031	10K		Washer	A10096-5 #6, Split (Qty 2)
R906	R1006	OPEN			Screw	A10240-0608 Stainless (Qty 2)
R907	R1007	OPEN			J1	C 7593-4 5 Pin Header
R908	R1008	OPEN			J2	C 4508-5 16 Pin Socket
R909	R1009	A10266-4741	470K		J11	C 7526-4 3 Pin Header
R910	R1010	A10266-4741	470K		J100 J200	C 6777-4 Phone Jack (Qty 2)
R911	R1011	A10266-1521	1.5K		Cover	C 6778-2 Ph Jk Cover (Qty 2)
R912	R1012	A10266-4711	470		J500 J800	D 6619-7 10 Inch Ribbon
R913	R1013	A10266-1051	1M		J600 J700	D 6620-5 6 Inch Ribbon
R914	R1014	A10266-1051	1M		Cable Tie	C 1811-6 (Qty 4)
R915	R1015	A10266-2201	22		TP 1	C 9450-5 Hdr, 6 pin RT Angle
R916	R1016	A10266-2201	22		Spacer	C 9225-1 Plastic (Qty 5)
R917	R1017	A10265-10021	10K 1%			
R918	R1018	A10265-10021	10K 1%			
R919	R1019	A10265-10021	10K 1%			
R920	R1020	A10265-10021	10K 1%			
R921	R1021	C 9079-2	200 Pot (CMR Null)			
R922	R1022	A10265-68101	681 1%			
R923	R1023	A10265-35711	3.57K 1%			
R924	R1024	A10265-66501	665 1%			
R925	R1025	A10265-10031	100K 1%			
R926	R1026	A10265-66501	665 1%			
R927	R1027	A10265-10031	100K 1%			
R928	R1028	A10265-35711	3.57K 1%			
R929	R1029	A10266-1241	120K			
R930	R1030	A10266-1241	120K			
Resistor Networks						
N101	N201	D 7944-8	Resistor Network			
N102	N202	D 6082-8	Resistor Network			

Q43272-6 Main Module (D 8283-0 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 8897-8	.1μF
C100	C200 C 5311-3	22μF
C101	C201 C 9464-6	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6805-3	.022μF
C105	C205 C 6812-9	47pF
C106	C206 C 6812-9	47pF
C107	C207 C 8897-8	.1μF
C108	C208 C 6814-5	12pF
C109	C209 C 7417-6	.0033μF
C110	C210 C 5362-6	2.2μF
C111	C211 C 8897-8	.1μF
C112	C212 C 8991-9	.47μF
C113	C213 C 8986-9	15μF
C114	C214 C 8854-9	100μF
C115	C215 C 8854-9	100μF
C116	C216 C 8986-9	15μF
C117	C217 C 8991-9	.47μF
C118	C218 C 6814-5	12pF
C119	C219 C 6802-0	.47μF
C120	C220 C 8897-8	.1μF
C122	C222 C 6811-1	100pF
C123	C223 C 6812-9	47pF
C124	C224 C 6812-9	47pF
C129	C229 C 6814-5	12pF
C130	C230 C 6813-7	27pF
C133	C233 C 6813-7	27pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6813-7	27pF
C139	C239 C 6813-7	27pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 8576-8	100μF
C145	C245 C 6812-9	47pF
C146	C246 C 6812-9	47pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C149	C249 C 6808-7	470pF
C150	C250 C 6806-1	.01μF
C151	C251 C 6806-1	.01μF
C152	C252 C 6950-7	82pF 5%
C153	C253 C 8897-8	.1μF
C154	C254 C 8426-6	.1μF 250V

C155	C255	C 8897-8	.1μF
C156	C256	C 8897-8	.1μF
C157	C257	C 6806-1	.01μF
C158	C258	C 6807-9	.001μF
C159	C259	C 6807-9	.001μF
C160	C260	C 6811-1	100pF
C161	C261	C 6811-1	100pF

Diodes

D1		C 2851-1	1N4004
D2		C 2851-1	1N4004
D3		C 2851-1	1N4004
D4		C 2851-1	1N4004
D5		C 2851-1	1N4004
D6		C 2851-1	1N4004
D7		C 2851-1	1N4004
D108	D208	C 3181-2	1N4148
D109	D209	C 3181-2	1N4148
D110	D210	C 3181-2	1N4148
D111	D211	C 5061-4	1N3070
D112	D212	C 3181-2	1N4148
D113	D213	C 3181-2	1N4148
D114	D214	C 3181-2	1N4148
D115	D215	C 3181-2	1N4148
D120	D220	C 3181-2	1N4148
D121	D221	C 3181-2	1N4148
D122	D222	C 3181-2	1N4148
D123	D223	C 5061-4	1N3070
D124	D224	C 3181-2	1N4148
D125	D225	C 3181-2	1N4148
D126	D226	C 5061-4	1N3070
D127	D227	C 5061-4	1N3070
D128	D228	C 5061-4	1N3070
D129	D229	C 3181-2	1N4148
D130	D230	C 3181-2	1N4148
D131	D231	C 3181-2	1N4148
D132	D232	C 3181-2	1N4148
D133	D233	C 3181-2	1N4148
D134	D234	C 3181-2	1N4148

Transistors

Q100	Q200	D 2961-7	NPN 2N3859A
Q100	Q200	A10266-9131	Resistor, 91K
Q101	Q201	C 3578-9	PNP MPSA93
Q102	Q202	C 3810-6	NPN MPSA43
Q103	Q203	C 3786-8	PNP PN4250
Q103	Q203	A10266-9131	Resistor, 91K
Q105	Q205	C 3578-9	PNP MPSA93
Q106	Q206	C 3625-8	NPN 2N4125
Q107	Q207	C 3786-8	PNP PN4250
Q108	Q208	C 5891-4	NPN MTS105
Q109	Q209	D 2961-7	NPN 2N3859A

Q43272-6 Main Module (D 8283-0 board) Parts List Cont.

Q110	Q210	C 3810-6	NPN MPSA43
Q112	Q212	C 3625-8	NPN 2N4125
Q113	Q213	C 3625-8	NPN 2N4125
Q115	Q215	D 2962-5	NPN MPS8097
Q116	Q216	C 3786-8	PNP PN4250
Q117	Q217	D 2961-7	NPN 2N3859A
Q118	Q218	D 2961-7	NPN 2N3859A
Q119	Q219	C 3625-8	NPN 2N4125
Q120	Q220	C 3625-8	NPN 2N4125
Q121	Q221	C 7458-0	NPN 2N4123
Q122	Q222	C 7458-0	NPN 2N4123
Q123	Q223	C 7458-0	NPN 2N4123
Q124	Q224	C 3625-8	NPN 2N4125
Q125	Q225	C 3786-8	PNP PN4250A
Q126	Q226	C 5891-4	NPN MTS105

Resistors

R1		A10265-53621	53.6K 1%
R2		C 7340-0	24 5W
R3		C 7340-0	24 5W
R4		A10265-46421	46.4K 1%
R7		A10266-1041	100K
R8		A10266-2031	20K
R9		A10266-5121	5.1K
R10		OPEN	
R16		A10266-5121	5.1K
R17		A10266-2031	20K
R18		A10266-1041	100K
R100	R200	C 7592-6	4 Pin Header
R101	R201	A10265-49911	4.99K 1%
R102	R202	A10266-5111	510
R103	R203	A10265-10031	100K 1%
R104	R204	A10266-2721	2.7K
R105	R205	A10266-2721	2.7K
R106	R206	A10266-1231	12K
R107	R207	A10266-6831	68K
R108	R208	A10266-8211	820
R109	R209	A10266-5601	56
R110	R210	A10266-6831	68K
R111	R211	A10266-1231	12K
R112	R212	A10266-5131	51K
R113	R213	A10266-4721	4.7K
R114	R214	A10266-4721	4.7K
R115	R215	A10266-3341	330K
R116	R216	A10266-2751	2.7M
R117	R217	A10266-4731	47K
R118	R218	A10265-28701	287 1%
R119	R219	A10265-80601	806 1%
R120	R220	A10265-28701	287 1%
R121	R221	C 5062-2	100K Pot (-ODEP)
R122	R222	A10266-2741	270K
R123	R223	A10266-2732	27K .5W

R124	R224	A10266-6821	6.8K
R125	R225	C 7782-3	100 Flame Proof
R126	R226	C 7782-3	100 Flame Proof
R127	R227	A10266-6821	6.8K
R128	R228	A10266-1331	13K
R129	R229	A10266-1041	100K
R130	R230	A10266-1041	100K
R131	R231	A10266-1331	13K
R132	R232	C 5062-2	100K Pot (+ODEP)
R133	R233	A10266-2741	270K
R134	R234	A10266-2732	27K .5W
R135	R235	C 7782-3	100 Flame Proof
R136	R236	A10266-6821	6.8K
R137	R237	C 7782-3	100 Flame Proof
R138	R238	A10266-6821	6.8K
R139	R239	A10266-8211	820
R140	R240	A10266-5601	56
R141	R241	A10266-1541	150K
R142	R242	A10266-1541	150K
R143	R243	A10266-1041	100K
R144	R244	A10266-1041	100K
R145	R245	A10266-2251	2.2M
R146	R246	A10266-1231	12K
R147	R247	C 8836-6	100 .5W Flame Proof
R148	R248	A10266-2721	2.7K
R149	R249	C 8836-6	100 .5W Flame Proof
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1231	12K
R152	R252	A10265-11521	11.5K 1%
R153	R253	JUMPER	JUMPER
R154	R254	C 8261-7	121K 0.1%
R155	R255	A10266-1321	1.3K
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10265-11321	11.3K 1%
R159	R259	A10266-1021	1K
R160	R260	C 8260-9	10K 0.1%
R161	R261	A10266-4701	47
R162	R262	A10266-4701	47
R163	R263	C 8261-7	121K 0.1%
R164	R264	C 8260-9	10K 0.1%
R165	R265	C 8261-7	121K 0.1%
R166	R266	A10266-2251	2.2M
R167	R267	A10265-10011	1K 1%
R168	R268	A10265-10011	1K 1%
R170	R270	A10265-10011	1K 1%
R171	R271	A10265-10011	1K 1%
R173	R273	C 8260-9	10K 0.1%
R174	R274	A10265-24921	24.9K 1%
R175	R265	A10265-78711	7.87K 1%
R176	R276	A10265-24921	24.9K 1%
R177	R277	A10265-22121	22.1K 1%

Q43272-6 Main Module (D 8283-0 board) Parts List Cont.

R179	R279	A10266-1321	1.3K	<div><div>Switches</div><div>S2C 7325-1Switch / Ground</div><div>S3C 7960-5Sensitivity</div><div>S4C 6781-6Switch, Stereo/Mono</div><div>IC's</div><div>U1C 5095-2UA7815</div><div>U2C 5096-0UA7915</div><div>U100U200C 6911-9UPA75</div><div>U101U201C 4345-2LM339</div><div>U102U202C 4345-2LM339</div><div>U103U203C 6910-1UPA76</div><div>U104U204C 7558-7MC33079P</div><div>Misc.</div><div>BoardD 8283-0</div><div>SocketC 3450-114 Pin (Qty 6)</div><div>NutA10102-5Hex 6-32 (Qty 2)</div><div>HeatsinkC 5341-0TO-220 (Qty 2)</div><div>SpreaderC 6541-4Torque Sprdr (Qty 2)</div><div>WasherA10096-5#6, Split (Qty 2)</div><div>ScrewA10240-0608Stainless (Qty 2)</div><div>J1C 7593-45 Pin Header</div><div>J2C 4508-516 Pin Socket</div><div>J11C 7526-43 Pin Header</div><div>J100J200C 6777-4Phone Jack (Qty 2)</div><div>CoverC 6778-2Ph Jk Cover (Qty 2)</div><div>J500J800D 6619-710 Inch Ribbon</div><div>J600J700D 6620-56 Inch Ribbon</div><div>Cable TieC 1811-6(Qty 4)</div><div>TP 1C 9450-5Hdr, 6 pin RT Angle</div><div>SpacerC 9225-1Plastic (Qty 5)</div></div>
R180	R280	A10266-4711	470	
R181	R281	A10266-4721	4.7K	
R182	R282	A10266-2201	22	
R183	R283	A10266-2421	2.4K	
R184	R284	A10266-4741	470K	
R185	R285	A10266-2421	2.4K	
R186	R286	A10266-2751	2.7M	
R187	R287	A10266-3631	36K	
R188	R288	A10266-3631	36K	
R189	R289	A10266-2731	27K	
R190	R290	A10266-2051	2M	
R191	R291	A10266-3331	33K	
R192	R292	A10266-1031	10K	
R193	R293	A10266-1031	10K	
R194	R294	A10266-1041	100K	
R195	R295	A10266-3021	3K	
R196	R296	A10266-4721	4.7K	
R197	R297	A10266-1031	10K	
R198	R298	A10266-4721	4.7K	
R199	R299	A10266-1031	10K	
R906	R1006	OPEN		
R907	R1007	OPEN		
R908	R1008	OPEN		
R909	R1009	A10266-4741	470K	
R910	R1010	A10266-4741	470K	
R911	R1011	A10266-1521	1.5K	
R912	R1012	A10266-4711	470	
R913	R1013	A10266-1051	1M	
R914	R1014	A10266-5141	510K	
R915	R1015	A10266-2201	22	
R916	R1016	A10266-2201	22	
R917	R1017	A10265-10021	10K 1%	
R918	R1018	A10265-10021	10K 1%	
R919	R1019	A10265-10021	10K 1%	
R920	R1020	A10265-10021	10K 1%	
R921	R1021	C 9079-2	200 Pot (CMR Null)	
R922	R1022	A10265-68101	681 1%	
R923	R1023	A10265-35711	3.57K 1%	
R924	R1024	A10265-60401	604 1%	
R925	R1025	A10265-10031	100K 1%	
R926	R1026	A10265-60401	604 1%	
R927	R1027	A10265-10031	100K 1%	
R928	R1028	A10265-35711	3.57K 1%	
R929	R1029	A10266-1241	120K	
R930	R1030	A10266-1241	120K	
Resistor Networks				
N101	N201	D 7944-8	Resistor Network	
N102	N202	D 6082-8	Resistor Network	

Q43257-7 Main Module (D 8369-7 board) Parts List

Capacitors

C1	C 4303-1	1000μF
C2	C 3913-8	470μF
C4	C 6802-0	.47μF
C5	C 6806-1	.01μF
C6	C 6806-1	.01μF
C7	C 8897-8	.1μF
C100	C200 C 5311-3	22μF
C101	C201 C 9464-6	10pF
C103	C203 C 6805-3	.022μF
C104	C204 C 6805-3	.022μF
C105	C205 C 6812-9	47pF
C106	C206 C 6812-9	47pF
C107	C207 C 8897-8	.1μF
C108	C208 C 6814-5	12pF
C109	C209 C 7417-6	.0033μF
C110	C210 C 5362-6	2.2μF
C111	C211 C 8897-8	.1μF
C112	C212 C 8991-9	.47μF
C113	C213 C 8986-9	15μF
C114	C214 C 8854-9	100μF
C115	C215 C 8854-9	100μF
C116	C216 C 8986-9	15μF
C117	C217 C 8991-9	.47μF
C118	C218 C 6814-5	12pF
C119	C219 C 6802-0	.47μF
C120	C220 C 8897-8	.1μF
C122	C222 C 6811-1	100pF
C123	C223 C 6812-9	47pF
C124	C224 C 6812-9	47pF
C129	C229 C 6814-5	12pF
C130	C230 C 6813-7	27pF
C133	C233 C 6813-7	27pF
C134	C234 C 6805-3	.022μF
C135	C235 C 6805-3	.022μF
C136	C236 C 6808-7	470pF
C137	C237 C 6808-7	470pF
C138	C238 C 6813-7	27pF
C139	C239 C 6813-7	27pF
C140	C240 C 6812-9	47pF
C141	C241 C 6812-9	47pF
C144	C244 C 8576-8	100μF
C145	C245 C 6812-9	47pF
C146	C246 C 6812-9	47pF
C147	C247 C 6806-1	.01μF
C148	C248 C 6810-3	180pF
C149	C249 C 6808-7	470pF
C150	C250 C 6806-1	.01μF
C151	C251 C 6806-1	.01μF
C152	C252 C 6950-7	82pF 5%
C153	C253 C 8897-8	.1μF
C154	C254 A10434-104JD	.1μF 250V

C155	C255	C 8897-8	.1μF
C156	C256	C 8897-8	.1μF
C157	C257	C 6806-1	.01μF
C158	C258	C 6807-9	.001μF
C159	C259	C 6807-9	.001μF
C160	C260	C 6811-1	100pF
C161	C261	C 6811-1	100pF

Diodes

D1		C 2851-1	1N4004
D2		C 2851-1	1N4004
D3		C 2851-1	1N4004
D4		C 2851-1	1N4004
D5		C 2851-1	1N4004
D6		C 2851-1	1N4004
D7		C 2851-1	1N4004
D108	D208	C 3181-2	1N4148
D109	D209	C 3181-2	1N4148
D110	D210	C 3181-2	1N4148
D111	D211	C 5061-4	1N3070
D112	D212	C 3181-2	1N4148
D113	D213	C 3181-2	1N4148
D114	D214	C 3181-2	1N4148
D115	D215	C 3181-2	1N4148
D120	D220	C 3181-2	1N4148
D121	D221	C 3181-2	1N4148
D122	D222	C 3181-2	1N4148
D123	D223	C 5061-4	1N3070
D124	D224	C 3181-2	1N4148
D125	D225	C 3181-2	1N4148
D126	D226	C 5061-4	1N3070
D127	D227	C 5061-4	1N3070
D128	D228	C 5061-4	1N3070
D129	D229	C 3181-2	1N4148
D130	D230	C 3181-2	1N4148
D131	D231	C 3181-2	1N4148
D132	D232	C 3181-2	1N4148
D133	D233	C 3181-2	1N4148
D134	D234	C 3181-2	1N4148

Transistors

Q100	Q200	D 2961-7	NPN 2N3859A
Q101	Q201	C 3578-9	PNP MPSA93
Q102	Q202	C 3810-6	NPN MPSA43
Q103	Q203	C 3786-8	PNP PN4250
Q105	Q205	C 3578-9	PNP MPSA93
Q106	Q206	C 3625-8	NPN 2N4125
Q107	Q207	C 3786-8	PNP PN4250
Q108	Q208	C 5891-4	NPN MTS105
Q109	Q209	D 2961-7	NPN 2N3859A
Q110	Q210	C 3810-6	NPN MPSA43
Q112	Q212	C 3625-8	NPN 2N4125

Q43257-7 Main Module (D 8369-7 board) Parts List Cont.

Q113	Q213	C 3625-8	NPN 2N4125
Q115	Q215	D 2962-5	NPN MPS8097
Q116	Q216	C 3786-8	PNP PN4250
Q117	Q217	D 2961-7	NPN 2N3859A
Q118	Q218	D 2961-7	NPN 2N3859A
Q119	Q219	C 3625-8	NPN 2N4125
Q120	Q220	C 3625-8	NPN 2N4125
Q121	Q221	C 7458-0	NPN 2N4123
Q122	Q222	C 7458-0	NPN 2N4123
Q123	Q223	C 7458-0	NPN 2N4123
Q124	Q224	C 3625-8	NPN 2N4125
Q125	Q225	C 3786-8	PNP PN4250A
Q126	Q226	C 5891-4	NPN MTS105

Resistors

R1		A10265-53621	53.6K 1%
R2		C 7340-0	24 5W
R3		C 7340-0	24 5W
R4		A10265-46421	46.4K 1%
R7		A10266-1041	100K
R8		A10266-2031	20K
R9		A10266-5121	5.1K
R10		OPEN	
R16		A10266-5121	5.1K
R17		A10266-2031	20K
R18		A10266-1041	100K
R101	R201	A10265-49911	4.99K 1%
R102	R202	A10266-5111	510
R103	R203	A10265-10031	100K 1%
R104	R204	A10266-2721	2.7K
R105	R205	A10266-2721	2.7K
R106	R206	A10266-1231	12K
R107	R207	A10266-6831	68K
R108	R208	A10266-80601	806 1%
R109	R209	A10266-5601	56
R110	R210	A10266-6831	68K
R111	R211	A10266-1231	12K
R112	R212	A10266-5131	51K
R113	R213	A10266-4721	4.7K
R114	R214	A10266-4721	4.7K
R115	R215	A10266-3341	330K
R116	R216	A10266-2751	2.7M
R117	R217	A10266-46411	4.64K 1%
R118	R218	A10265-28701	287 1%
R119	R219	A10265-80601	806 1%
R120	R220	A10265-28701	287 1%
R121	R221	C 5062-2	100K Pot (-ODEP)
R122	R222	A10266-2741	270K
R123	R223	A10266-2732	27K .5W
R124	R224	A10266-6821	6.8K
R125	R225	C 8836-6	100 Flame Proof
R126	R226	C 8836-6	100 Flame Proof

R127	R227	A10266-6821	6.8K
R128	R228	A10266-1331	13K
R129	R229	A10266-1041	100K
R130	R230	A10266-1041	100K
R131	R231	A10266-1331	13K
R132	R232	C 5062-2	100K Pot (+ODEP)
R133	R233	A10266-2741	270K
R134	R234	A10266-2732	27K .5W
R135	R235	C 8836-6	100 Flame Proof
R136	R236	A10266-6821	6.8K
R137	R237	C 8836-6	100 Flame Proof
R138	R238	A10266-6821	6.8K
R139	R239	A10266-80601	806 1%
R140	R240	A10266-5601	56
R141	R241	A10266-1541	150K
R142	R242	A10266-1541	150K
R143	R243	A10266-1041	100K
R144	R244	A10266-1041	100K
R145	R245	A10266-3351	3.3M
R146	R246	A10266-1231	12K
R147	R247	C 8836-6	100 .5W Flame Proof
R148	R248	A10266-2721	2.7K
R149	R249	C 8836-6	100 .5W Flame Proof
R150	R250	A10266-2721	2.7K
R151	R251	A10266-1231	12K
R152	R252	A10265-11521	11.5K 1%
R153	R253	JUMPER	JUMPER
R154	R254	C 8261-7	121K 0.1%
R155	R255	A10266-1321	1.3K
R156	R256	A10266-1321	1.3K
R157	R257	A10266-1321	1.3K
R158	R258	A10265-11321	11.3K 1%
R159	R259	A10266-1021	1K
R160	R260	C 8260-9	10K 0.1%
R161	R261	A10266-4701	47
R162	R262	A10266-4701	47
R163	R263	C 8261-7	121K 0.1%
R164	R264	C 8260-9	10K 0.1%
R165	R265	C 8261-7	121K 0.1%
R166	R266	A10266-3351	3.3M
R167	R267	A10265-10011	1K 1%
R168	R268	A10265-10011	1K 1%
R170	R270	A10265-10011	1K 1%
R171	R271	A10265-10011	1K 1%
R173	R273	C 8260-9	10K 0.1%
R174	R274	A10265-24921	24.9K 1%
R175	R265	A10265-78711	7.87K 1%
R176	R276	A10265-24921	24.9K 1%
R177	R277	A10265-19121	19.1K 1%
R178	R278	A10266-2021	2K
R179	R279	A10266-1321	1.3K
R180	R280	A10266-4711	470

Q43257-7 Main Module (D 8369-7 board) Parts List Cont.

R181	R281	A10266-4721	4.7K
R182	R282	A10266-2201	22
R183	R283	A10266-2421	2.4K
R184	R284	A10266-4741	470K
R185	R285	A10266-2421	2.4K
R186	R286	A10266-2751	2.7M
R187	R287	A10266-3631	36K
R188	R288	A10266-3631	36K
R189	R289	A10266-2731	27K
R190	R290	A10266-2051	2M
R191	R291	A10266-1831	18K
R192	R292	A10266-6221	6.2K
R193	R293	A10266-6221	6.2K
R194	R294	A10266-1041	100K
R195	R295	A10266-3021	3K
R196	R296	A10266-4721	4.7K
R197	R297	A10266-1031	10K
R198	R298	A10266-4721	4.7K
R199	R299	A10266-1031	10K
R300	R400	A10265-10031	100K
R301	R401	A10265-10031	100K
R906	R1006	OPEN	
R907	R1007	OPEN	
R908	R1008	OPEN	
R909	R1009	A10266-4741	470K
R910	R1010	A10266-4741	470K
R911	R1011	A10266-1521	1.5K
R912	R1012	A10266-4711	470
R913	R1013	A10266-1051	1M
R914	R1014	A10266-5141	510K
R915	R1015	A10266-2201	22
R916	R1016	A10266-2201	22
R917	R1017	A10265-10021	10K 1%
R918	R1018	A10265-10021	10K 1%
R919	R1019	A10265-10021	10K 1%
R920	R1020	A10265-10021	10K 1%
R921	R1021	C 9079-2	200 Pot (CMR Null)
R922	R1022	A10265-68101	681 1%
R923	R1023	A10265-35711	3.57K 1%
R924	R1024	A10265-60401	604 1%
R925	R1025	A10265-10031	100K 1%
R926	R1026	A10265-60401	604 1%
R927	R1027	A10265-10031	100K 1%
R928	R1028	A10265-35711	3.57K 1%
R929	R1029	A10266-1241	120K
R930	R1030	A10266-1241	120K

Resistor Networks

N101	N201	D 7944-8	Resistor Network
N102	N202	D 6082-8	Resistor Network

Switches





S2	C 7325-1	Switch / Ground
S3	C 7960-5	Sensitivity
S4	C 6781-6	Switch, Stereo/Mono

IC's

U1		C 5095-2	UA7815
U2		C 5096-0	UA7915
U100	U200	C 6911-9	UPA75
U101	U201	C 4345-2	LM339
U102	U202	C 4345-2	LM339
U103	U203	C 6910-1	UPA76
U104	U204	C 7558-7	MC33079P

Misc.



Board	D 8369-7		
Socket	C 3450-1	14 Pin (Qty 6)	
Nut	A10102-5	Hex 6-32 (Qty 2)	
Heatsink	C 9494-3	TO-220 (Qty 2)	
Spreader	C 6541-4	Torque Sprdr (Qty 2)	
Washer	A10096-5	#6, Split (Qty 2)	
Screw	A10240-0608	Stainless (Qty 2)	
J1	C 7593-4	5 Pin Header	
J2	C 4508-5	16 Pin Socket	
J11	C 7526-4	3 Pin Header	
J100	J200	C 6777-4	Phone Jack (Qty 2)
J101	J201	C 7526-4	3 Pin Header
Cover	C 6778-2	Ph Jk Cover (Qty 2)	
J500	J800	D 6619-7	10 Inch Ribbon
J600	J700	D 6620-5	6 Inch Ribbon
Cable Tie	C 1811-6	(Qty 4)	
TP 1	C 9450-5	Hdr, 6 pin RT Angle	
Spacer	C 9944-7	Nylon (Qty 5)	



INACTIVE
For Reference Use Only

UNCONTROLLED
UNLESS OTHERWISE NOTED IN THE INK BY CH AS A
CONTROLLED COPY, COPIES OF THESE DOCUMENTS
INCLUDING ASSOCIATED ELECTRONIC REPRODUCTIONS
AND FOR REPRODUCTION ONLY.
THESE DRAWINGS AND SPECIFICATIONS ARE THE
PROPERTY OF CROWN INTERNATIONAL, INC. AND
SHALL NOT BE REPRODUCED, COPIED, OR USED
AS THE BASIS FOR THE MANUFACTURE OR SALE
OF APPARATUS OR DEVICES WITHOUT PERMISSION.


DWN		JAW	04/14/00		1718 W. WISHAWAKA RD. ELIZABETH, NJ 07201 PHONE (201) 284-8888 WWW.CROWNINTL.COM
CHK		KW	05-28-00		
DISTRIB		CM	JM	TITLE	
FILENAME		SCH. MA2400 MAIN 126063-1			
D		126064		REV	
DO NOT SCALE DRAWING		SCALE	NONE	PROJ. NO.	ME28450
		SHEET		1 OF 2	




COMMON	
LAST USED	OBSOLETE
C7	
D7	
R1B	R5,6,11-15
S4	
U2	


CHANNEL 1	
LAST USED	OBSOLETE
C157	C121,131,132,142
D132	D100-103,116,118,119
N102	N100
Q124	Q104,111,114
R199	R100,169,172,178
RS21	RS00-905
U184	

- NOTES :
1. ALL RESISTORS ARE IN OHMS, 1/4W, 5% UNLESS OTHERWISE SPECIFIED.
 2. ALL CAPACITORS ARE IN MICROFARADS UNLESS OTHERWISE SPECIFIED.
 3. CHANNEL 1 SHOWN, FOR CHANNEL 2, ADD 100 TO REFERENCE DESIGNATORS. (EXAMPLE : CHANNEL 1 R101 WOULD BE CHANNEL 2 R201) CONNECTOR AND IC PIN NUMBERS FOR CHANNEL 2 ARE SHOWN IN PARENTHESIS WHEN THEY DIFFER FROM CHANNEL 1.
 4. ALL DIODES ARE 1N4149 UNLESS OTHERWISE SPECIFIED.
 5. ON J500 AND J700 THE STRIPED WIRE GOES TO PIN 10 OF THE BOARD AND THE PIN NUMBERS MOLDED ON THE CABLE SOCKET ARE REVERSED FROM THE PIN NUMBERS ON THE BOARD AND THE SCHEMATIC.
 6. STANDARD UNIT HAS R10 OPEN. INSTALL JUMPER IN R10 TO DISABLE CHANNEL 2 SIGNAL/IOC LIGHT IN PARALLEL MONO MODE.
 7. POWER SUPPLY VOLTAGES SHOWN UNDER NO LOAD CONDITION.
 8. CHANNEL 2 PRE-DRIVER BASES LOOP THROUGH STEREO-MONO SWITCH S4, SECTIONS E AND F.
 9. THIS SCHEMATIC REVISION APPLIES TO MAIN BOARD D8369-7 / MODULE Q43257-7 AND OUTPUT BOARD P10433-4 / MODULE Q43358-3.







REVISION HISTORY									
E.C. N.	ZONE	REV	DESCRIPTION	DATE	DWN	CHK	CM	PE	
		C	ON SHEET 2, C5 WAS 1000 NOW IS C1 AT 470	08/03/94	LCD			JM	
EAT 94-174		D	C109, C209, WERE 330PF R177, R277 WERE 22.1K	11/07/94	LCD			JM	
EAT 95-244		E	ADD R341, 342, 343, 344, 345, 346, 441, 442, 443.	09/11/95	LCD			JM	
EAT 95-217		F	R312, R314, R412, R414 WERE 1W NOW 2W	10/09/95	LCD			TS	
0808085		G	CHANGE DISPLAY CONN FROM DIP TO DUAL IN LINE DELETE DISPLAY BOARD CHANGE U100, 126, 300, 226 TO C 7450-B, CHANGE U100, 200 TO 103300-1, CHANGE U103, 203 TO 103300-1.	02/04/00	JAW	KL	LS		

DWN				LCD		12/08/93		 <div>crown INTERNATIONAL, INC.</div>	1718 W. MISHAWAKA RD. ELKHART IN. 46517 PHONE (219) 294-8000 WWW.CROWNINTL.COM								
CHK																	
CM																	
DISTRIBUTION									TITLE								
G				PE		JM			12-22-93		SCH, MA-2400/MA-2401						
FILENAME																	
TOLERANCE UNLESS OTHERWISE SPECIFIED									SIZE		DWG NO.		REV				
.00 = ±.02"									D		J0625-4		G				
.000 = ±.010"																	
DRILLS = ±.003"																	
DO NOT SCALE DRAWING								SCALE		NONE		PROJ NO.		MD26450		SHEET 1 OF 3	

UNCONTROLLED
UNLESS OTHERWISE MARKED IN RED INK BY CM AS A CONTROLLED COPY. COPIES OF THESE DOCUMENTS INCLUDING ASSOCIATED ELECTRONIC REPRODUCTIONS ARE FOR REFERENCE ONLY.
THESE DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF CROWN INTERNATIONAL, INC. AND SHALL NOT BE REPRODUCED, COPIED, OR USED AS THE BASIS FOR THE MANUFACTURE OR SALE OF APPARATUS OR DEVICES WITHOUT PERMISSION.

INACTIVE
For Reference Use Only



COMMON	
LAST USED	OBSOLETE
C7	
D7	
R1B	R5,6,11-15
S4	
U2	

CHANNEL 1	
LAST USED	OBSOLETE
C157	C121,131,132,142
D132	D100-103,116,118,119
N102	N100
Q124	Q104,111,114
R199	R100,169,172,178
RS21	RS00-905
U184	

- NOTES :
1. ALL RESISTORS ARE IN OHMS, 1/4W, 5% UNLESS OTHERWISE SPECIFIED.
 2. ALL CAPACITORS ARE IN MICROFARADS UNLESS OTHERWISE SPECIFIED.
 3. CHANNEL 1 SHOWN, FOR CHANNEL 2, ADD 100 TO REFERENCE DESIGNATORS. (EXAMPLE : CHANNEL 1 R101 WOULD BE CHANNEL 2 R201) CONNECTOR AND IC PIN NUMBERS FOR CHANNEL 2 ARE SHOWN IN PARENTHESIS WHEN THEY DIFFER FROM CHANNEL 1.
 4. ALL DIODES ARE 1N4149 UNLESS OTHERWISE SPECIFIED.
 5. ON J500 AND J700 THE STRIPED WIRE GOES TO PIN 10 OF THE BOARD AND THE PIN NUMBERS MOLDED ON THE CABLE SOCKET ARE REVERSED FROM THE PIN NUMBERS ON THE BOARD AND THE SCHEMATIC.
 6. STANDARD UNIT HAS R10 OPEN. INSTALL JUMPER IN R10 TO DISABLE CHANNEL 2 SIGNAL/IOC LIGHT IN PARALLEL MONO MODE.
 7. POWER SUPPLY VOLTAGES SHOWN UNDER NO LOAD CONDITION.
 8. CHANNEL 2 PRE-DRIVER BASES LOOP THROUGH STEREO-MONO SWITCH S4, SECTIONS E AND F.
 9. THIS SCHEMATIC REVISION APPLIES TO MAIN BOARD D8369-7 / MODULE Q43257-7 AND OUTPUT BOARD P10433-4 / MODULE Q43358-3.

